
HASSAN DISTRICT COOPERATIVE MILK PRODUCERS' UNION LTD, INDUSTRIAL ESTATE B M ROAD, HASSAN-573201, PHONE:08172-240628,240615

NATIONAL COMPETITIVE BIDDING FOR THE SUPPLY OF BMCU OF CAPACITY 5KL & 3KL

BID REFERENCE	BMCU
DATE OF COMMENCEMENT OF SALE OF BIDDING DOCUMENT	02.04.2018
PRE BID MEETING	20.04.2018 at 3:00pm
LAST DATE FOR SALE OF BIDDING DOCUMENT	15.05.2018
LAST DATE AND TIME FOR THE RECEIPT OF BIDS	16.05.2018 at 4:00pm
DATE AND TIME OF OPENING OF BIDS	16.05.2018 at 4:30pm
PLACE OF OPENING OF BIDS	Conference Hall-2, Hassan Cooperative Milk Producers Societies Union Ltd, Hassan-573201

ADDRESS FOR COMMUNICATION
HASSAN DISTRICT COOPERATIVE MILK PRODUCERS' UNION LTD,
INDUSTRIAL ESTATE, B M ROAD, HASSAN-573201.
PHONE: 02742 253881 TO 85, FAX: 02742 252723



NATIONAL COMPETITIVE BIDDING FOR THE SUPPLY OF BMCU

INVITATION FOR BIDS (IFB)

Date : 02.04.2018

Credit No. : 5074- IN

IFB No. : NCB-1VBMPS –BMCU 5KL & 3KL

- The Government of India has received a Credit from the International Development Association in various currencies towards the cost of NDP-1. THE HASSAN COOPERATIVE MILK PRODUCERS SOCIETIES UNION LTD, HASSAN an EIA of the project intends to apply part of the proceeds of this credit to eligible payments under the contracts for which this Invitation for Bids is issued.
- 2. THE HASSAN COOPERATIVE MILK PRODUCERS SOCIETIES UNION LTD, HASSAN (*Purchaser*) now invites sealed bids from eligible bidders for supply of Milk Analyzer..
- 3. Bidding will be conducted through the National Competitive Bidding (NCB) procedures of the World Bank. The provisions in the Instructions to Bidders and in the General Conditions of contract are based on the provisions of the World Bank Standard Bidding Document Procurement of Goods.
- 4. Interested eligible Bidders may obtain further information from and inspect the bidding documents at the office of the HASSAN COOPERATIVE MILK PRODUCERS SOCIETIES UNION LTD, HASSAN-573201, KARNATAKA, INDIA
- 5. A complete set of bidding documents may be purchased by any interested eligible bidder on the submission of a written application to the above office and upon payment of a non-refundable fee as indicated below in the form of a Demand Draft in favour of HASSAN COOPERATIVE MILK PRODUCERS SOCIETIES UNION LTD, HASSAN, payable at HASSAN. Tender Document will also be available on our website: www.kmfnandini.coop, however bidder opting to submitted document will be required to submit Demand Draft in lieu of non refundable tender fee along with bid. Tender without tender fee will be considered as non responsive.
- 6. The bidding document may be obtained from the office of HASSAN COOPERATIVE MILK PRODUCERS SOCIETIES UNION LTD, HASSAN-573201, during office hours namely, from 10:00AM hrs to 3:00PM hrs, on all working days either in person or by post. HASSAN COOPERATIVE MILK PRODUCERS SOCIETIES UNION LTD, HASSAN 573201

be not be held responsible for the postal delay, if any, in the delivery of documents or non-receipt of the same.

(a) Price of bidding document

(non-refundable)

: Rs.1000/-

(b) Postal charges, inland : Rs. 100/-

(c) Postal charges, overseas : Rs.500/-

(d) Date of commencement of : 02.04.2018

sale of bidding document

(e) Last date for sale of : 15.05.2018

Bidding document

(f) Last date and time for : 16.05.2018 at 4:00 pm

receipt of bids

(g) Time and date of : 16.05.2018 at 4:30 pm

Opening of bids

(h) Place of opening of bids : HASSAN DISTRICT COOPERATIVE MILK PRODUCERS' UNIONLTD,

HASSAN - 573201, PHONE: 02742 253881 TO 85, FAX: 02742 252723(i)

(i) Address for communication:

HASSAN DISTRICT COOPERATIVE MILK PRODUCERS' UNION LTD, INDUSTRIAL ESTATE, B M ROAD, HASSAN-573201


PHONE: 08172-240628 FAX: 08172-240640


7. All bids must be accompanied by a bid security as specified in the bid document and must be delivered to the above office at the date and time indicated above. Electronic bidding will not be permitted. Late bids will be rejected.

- 8. Bids will be opened in the presence of Bidders' representatives who choose to attend on the specified date and time.
- 9. In the event of the date specified for bid receipt and opening being declared as a closed holiday for purchaser's office, the due date for submission of bids and opening of bids will be the following working day at the appointed times.

TABLE OF CONTENT

PART 1 – BIDDING PROCEDURES	
SECTION I - INSTRUCTIONS TO BIDDERS [ITB]	1-7
SECTION II - BIDDING DATA SHEET	32
SECTION III. EVALUATION AND QUALIFICATION CRITERIA	36
SECTION IV – BIDDING FORMS	39
SECTION V. – ELIGIBLE COUNTRIES	49
PART 2 - SUPPLY REQUIREMENTS	50
SECTION VI – SCHEDULE OF REQUIREMENTS	51
PART 3 – CONTRACT	79
SECTION VII – GENERAL CONDITIONS OF CONTRACT	80
SECTION VIII. SPECIAL CONDITIONS OF CONTRACT	97
SECTION IX – CONTRACT FORMS	103





Section I. Instructions to Bidders

Table of Clauses

A.	GENER	AL	11
	1.	SCOPE OF BID	11
	2.	Source of Funds	11
	3.	FRAUD AND CORRUPTION	11
	4.	Eligible Bidders	13
	5.	ELIGIBLE GOODS AND RELATED SERVICES	14
В.	CONTE	NTS OF BIDDING DOCUMENTS	14
	6.	SECTIONS OF BIDDING DOCUMENTS	
	7.	CLARIFICATION OF BIDDING DOCUMENTS	
	8.	AMENDMENT OF BIDDING DOCUMENTS	15
	DDEDA	RATION OF BIDS	17
C.			
	9.	COST OF BIDDING	
	10.	LANGUAGE OF BID	
	11.	DOCUMENTS COMPRISING THE BID	
	12.	BID SUBMISSION FORM AND PRICE SCHEDULES	
	13.	ALTERNATIVE BIDS	
	14.	BID PRICES AND DISCOUNTS	
	15.	CURRENCIES OF BID	
	16.	DOCUMENTS ESTABLISHING THE ELIGIBILITY OF THE BIDDER	19
	17.	DOCUMENTS ESTABLISHING THE ELIGIBILITY OF THE GOODS AND RELATED	
		VICES	19
	18.	DOCUMENTS ESTABLISHING THE CONFORMITY OF THE GOODS AND RELATED	
	SERV	VICES	
	19.	DOCUMENTS ESTABLISHING THE QUALIFICATIONS OF THE BIDDER	19
	20.	PERIOD OF VALIDITY OF BIDS	20
	21.	BID SECURITY	20
	22.	FORMAT AND SIGNING OF BID	22
_			
D.		SSION AND OPENING OF BIDS	
	23.	SUBMISSION, SEALING AND MARKING OF BIDS	
	24.	DEADLINE FOR SUBMISSION OF BIDS	
	25.	Late Bids	
	26.	WITHDRAWAL, SUBSTITUTION, AND MODIFICATION OF BIDS	23
	27.	BID OPENING	24
T	TOTAL EL	ATION AND COMPADICON OF DIDC	25
L.		ATION AND COMPARISON OF BIDS	
	28.	Confidentiality	25
	29.	CLARIFICATION OF BIDS	23

	30. RESPONSIVENESS OF BIDS	.26
	31. Nonconformities, Errors, and Omissions	.26
	32. Preliminary Examination of Bids	.27
	33. EXAMINATION OF TERMS AND CONDITIONS; TECHNICAL EVALUATION	.27
	34. CONVERSION TO SINGLE CURRENCY- NOT USED	
	35. DOMESTIC PREFERENCE - NOT USED	.28
	36. EVALUATION OF BIDS	
	37. COMPARISON OF BIDS	.29
	38. POSTQUALIFICATION OF THE BIDDER	.29
(39. PURCHASER'S RIGHT TO ACCEPT ANY BID, AND TO REJECT ANY OR ALL BIDS	.30
F. AW	ARD OF CONTRACT	.30
	40. Award Criteria	.30
4	41. PURCHASER'S RIGHT TO VARY QUANTITIES AT TIME OF AWARD	.30
4	42. NOTIFICATION OF AWARD	.30
2	43. SIGNING OF CONTRACT	.31
2	44. PERFORMANCE SECURITY	.31

Section I. Instructions to Bidders

A. General

- 1. Scope of Bid
- 1.1 The Purchaser indicated in the Bidding Data Sheet (BDS), issues these Bidding Documents for the supply of Goods and Related Services incidental thereto as specified in Section VI, Schedule of Requirements. The name and identification number of this National Competitive Bidding (NCB) procurement are specified in the BDS. The name, identification, and number of lots of are provided in the BDS.
- 1.2 Throughout these Bidding Documents:
- (a) the term "in writing" means communicated in written form (e.g. by mail, e-mail, fax, telex) with proof of receipt;
- (b) if the context so requires, "singular" means "plural" and vice versa; and
- (c) "day" means calendar day.
- 2. Source of Funds
- 2.1 The Government of India (hereinafter called "Borrower") specified in the BDS has applied for or received financing (hereinafter called "funds") from the International Bank for Reconstruction and Development or the International Development Association (hereinafter called "the Bank") toward the cost of the project named in the BDS. The Borrower intends to apply a portion of the funds to eligible payments under the contract for which these Bidding Documents are issued.
- 2.2 Payments by the Bank will be made only at the request of the Borrower and upon approval by the Bank in accordance with the terms and conditions of the financing agreement between the Borrower and the Bank (hereinafter called the Loan Agreement), and will be subject in all respects to the terms and conditions of that Loan Agreement. The Loan Agreement prohibits a withdrawal from the loan account for the purpose of any payment to persons or entities, or for any import of goods, if such payment or import, to the knowledge of the Bank, is prohibited by decision of the United Nations Security Council taken under Chapter VII of the Charter of the United Nations. No party other than the Borrower shall derive any rights from the Loan Agreement or have any claim to the funds.
- 3. Fraud and Corruption
- 3.1 It is the Bank's policy to require that Borrowers (including beneficiaries of Bank loans), bidders, suppliers, contractors and

their agents (whether declared or not), sub-contractors, sub-consultants, service providers or suppliers, and any personnel thereof, observe the highest standard of ethics during the procurement and execution of Bank-financed contracts. In pursuance of this policy, the Bank:

- (a) defines, for the purposes of this provision, the terms set forth below as follows:
- (i) "corrupt practice" is the offering, giving, receiving or soliciting, directly or indirectly, of anything of value to influence improperly the actions of another party;
- (ii) "fraudulent practice" is any act or omission, including a misrepresentation, that knowingly or recklessly misleads, or attempts to mislead, a party to obtain a financial or other benefit or to avoid an obligation;
- (iii) "collusive practice" is an arrangement between two or more parties designed to achieve an improper purpose, including to influence improperly the actions of another party;
- (iv) "coercive practice" is impairing or harming, or threatening to impair or harm, directly or indirectly, any party or the property of the party to influence improperly the actions of a party;
- (v) "obstructive practice" is
- (aa) deliberately destroying, falsifying, altering or concealing of evidence material to the investigation or making false statements to investigators in order to materially impede a Bank investigation into allegations of a corrupt, fraudulent, coercive or collusive practice; and/or threatening, harassing or intimidating any party to prevent it from disclosing its knowledge of matters relevant to the investigation or from pursuing the investigation, or
- (bb) acts intended to materially impede the exercise of the Bank's inspection and audit rights provided for under paragraph 1.16(e) below.
- (b) will reject a proposal for award if it determines that the bidder recommended for award, or any of its personnel, or its agents, or its sub-consultants, sub-contractors, service providers, suppliers and/or their employees, has, directly or indirectly, engaged in corrupt, fraudulent, collusive, coercive or obstructive practices in competing for the contract in question;
- (c) will declare misprocurement and cancel the portion of the loan allocated to a contract if it determines at any time that representatives of the Borrower or of a recipient of any part of the proceeds of the loan engaged in corrupt, fraudulent, collusive, coercive or obstructive practices during the procurement or the

implementation of the contract in question, without the Borrower having taken timely and appropriate action satisfactory to the Bank to address such practices when they occur, including by failing to inform the Bank in a timely manner at the time they knew of the practices;

- (d) will sanction a firm or individual, at any time, in accordance with prevailing Bank's sanctions procedures, including by publicly declaring such firm or individual ineligible, either indefinitely or for a stated period of time: (i) to be awarded a Bank-financed contract; and (ii) to be a nominated sub-contractor, consultant, supplier or services provider of an otherwise eligible firm being awarded a Bank-financed contract:
- 3.2 Furthermore, Bidders shall be aware of the provision stated in Sub-Clause 35.1 (a) (iii) of the General Conditions of Contract.

4. Eligible Bidders

- 4.1 A Bidder, and all parties constituting the Bidder, may have the nationality of any country, subject to the restrictions specified in Section V, Eligible Countries. A Bidder shall be deemed to have the nationality of a country if the Bidder is a citizen or is constituted, incorporated, or registered and operates in conformity with the provisions of the laws of that country. This criterion shall also apply to the determination of the nationality of proposed subcontractors or suppliers for any part of the Contract including Related Services.
- 4.2 A Bidder shall not have a conflict of interest. All bidders found to have conflict of interest shall be disqualified. Bidders may be considered to have a conflict of interest with one or more parties in this bidding process, if they:
- (a) are or have been associated in the past, with a firm or any of its affiliates which have been engaged by the Purchaser to provide consulting services for the preparation of the design, specifications, and other documents to be used for the procurement of the goods to be purchased under these Bidding Documents; or
- (b) submit more than one bid in this bidding process, except for alternative offers permitted under ITB Clause 13. However, this does not limit the participation of subcontractors in more than one bid;
- 4.3 A Bidder that is under a declaration of ineligibility by the Bank in accordance with ITB Clause 3, at the date of contract award, shall be disqualified. The list of debarred firms is available at

the electronic address specified in the **BDS**.

- 4.4 A firm that has been determined to be ineligible by the Bank in relation to the Bank Guidelines On Preventing and Combating Fraud and Corruption in Projects Financed by IBRD Loans and IDA Credits and Grants shall be not be eligible to be awarded a contract.
- 4.5 Government-owned enterprises in the Borrower's Country shall be eligible only if they can establish that they (i) are legally and financially autonomous, (ii) operate under commercial law, and (iii) are not a dependent agency of the Purchaser or Borrower or Sub-Borrower.
- 4.6 Bidders shall provide such evidence of their continued eligibility satisfactory to the Purchaser, as the Purchaser shall reasonably request.

5. Eligible Goods and Related Services

- 5.1 All the Goods and Related Services to be supplied under the Contract and financed by the Bank may have their origin in any country in accordance with Section V, Eligible Countries.
- 5.2 For purposes of this Clause, the term "goods" includes commodities, raw material, machinery, equipment, and industrial plants; and "related services" includes services such as insurance, installation, training, and initial maintenance.
- 5.3 The term "origin" means the country where the goods have been mined, grown, cultivated, produced, manufactured or processed; or, through manufacture, processing, or assembly, another commercially recognized article results that differs substantially in its basic characteristics from its components.

B. Contents of Bidding Documents

6. Sections of Bidding Documents

6.1 The Bidding Documents consist of Parts 1, 2, and 3, which include all the Sections indicated below, and should be read in conjunction with any Addendum issued in accordance with ITB Clause 8.

PART 1 Bidding Procedures

- Section I. Instructions to Bidders (ITB)
- Section II. Bidding Data Sheet (BDS)
- Section III. Evaluation and Qualification Criteria

- Section IV. Bidding Forms
- Section V. Eligible Countries

PART 2 Supply Requirements

• Section VI. Schedule of Requirements

PART 3 Contract

- Section VII. General Conditions of Contract (GCC)
- Section VIII. Special Conditions of Contract (SCC)
- Section IX. Contract Forms
- 6.2 The Invitation for Bids issued by the Purchaser is not part of the Bidding Documents.
- 6.3 The Purchaser is not responsible for the completeness of the Bidding Documents and their addendum, if they were not obtained directly from the Purchaser.
- 6.4 The Bidder is expected to examine all instructions, forms, terms, and specifications in the Bidding Documents. Failure to furnish all information or documentation required by the Bidding Documents may result in the rejection of the bid.
- 7. Clarification of Bidding Documents
- 7.1 A prospective Bidder requiring any clarification of the Bidding Documents shall contact the Purchaser in writing at the Purchaser's address **specified in the BDS.** The Purchaser will respond in writing to any request for clarification, provided that such request is received no later than fifteen (15) days prior to the deadline for submission of bids. The Purchaser shall forward copies of its response to all those who have acquired the Bidding Documents directly from it, including a description of the inquiry but without identifying its source Should the Purchaser deem it necessary to amend the Bidding Documents as a result of a clarification, it shall do so following the procedure under ITB Clause 8 and ITB Sub-Clause 24.2.
- 8. Amendment of Bidding Documents
- 8.1 At any time prior to the deadline for submission of bids, the Purchaser may amend the Bidding Documents by issuing addendum.
- 8.2 Any addendum issued shall be part of the Bidding Documents and shall be communicated in writing to all who have obtained the Bidding Documents directly from the Purchaser.
- 8.3 To give prospective Bidders reasonable time in which to take an

addendum into account in preparing their bids, the Purchaser may, at its discretion, extend the deadline for the submission of bids, pursuant to ITB Sub-Clause 24.2

C. Preparation of Bids

9. Cost of Bidding

9.1 The Bidder shall bear all costs associated with the preparation and submission of its bid, and the Purchaser shall not be responsible or liable for those costs, regardless of the conduct or outcome of the bidding process.

10. Language of Bid

10.1 The Bid, as well as all correspondence and documents relating to the bid exchanged by the Bidder and the Purchaser, shall be written in English language. Supporting documents and printed literature that are part of the Bid may be in another language provided they are accompanied by an accurate translation of the relevant passages into English language, in which case, for purposes of interpretation of the Bid, such translation shall govern.

11. Documents Comprising the Bid

- 11.1 The Bid shall comprise the following:
- (a) Bid Submission Form and the applicable Price Schedules, in accordance with ITB Clauses 12, 14, and 15;
- (b) Bid Security, in accordance with ITB Clause 21, if required;
- (c) written confirmation authorizing the signatory of the Bid to commit the Bidder, in accordance with ITB Clause 22;
- (d) documentary evidence in accordance with ITB Clause 16 establishing the Bidder's eligibility to bid;
- (e) documentary evidence in accordance with ITB Clause 17, that the Goods and Related Services to be supplied by the Bidder are of eligible origin;
- (f) documentary evidence in accordance with ITB Clauses 18 and 30, that the Goods and Related Services conform to the Bidding Documents:
- (g) documentary evidence in accordance with ITB Clause 19 establishing the Bidder's qualifications to perform the contract if its bid is accepted; and
- (h) any other document **required in the BDS**.

12. Bid Submission Form and Price Schedules

12.1 The Bidder shall submit the Bid Submission Form using the form furnished in Section IV, Bidding Forms. This form must be completed without any alterations to its format, and no substitutes shall be accepted. All blank spaces shall be filled in with the information requested.

13. Alternative Bids

13.1 Unless otherwise **specified in the BDS**, alternative bids shall not be considered.

14. Bid Prices and Discounts

- 14.1 The prices and discounts quoted by the Bidder in the Bid Submission Form and in the Price Schedules shall conform to the requirements specified below.
- 14.2 A lots including the BMCU'S with all accessories must be listed and priced separately in the Price Schedules.
- 14.3 The price to be quoted in the Bid Submission Form shall be the total price of the bid, excluding any discounts offered.
- 14.4 The Bidder shall quote any unconditional discounts and indicate the method for their application in the Bid Submission Form.
- 14.5 The terms EXW and other similar terms shall be governed by the rules prescribed in the current edition of Incoterms, published by The International Chamber of Commerce, as specified in the **BDS.**
- 14.6 Prices shall be quoted as specified in the Price Schedule included in Section IV, Bidding Forms. The dis-aggregation of price components is required solely for the purpose of facilitating the comparison of bids by the Purchaser. This shall not in any way limit the Purchaser's right to contract on any of the terms offered. In quoting prices, the Bidder shall be free to use transportation through carriers registered in any eligible country, in accordance with Section V Eligible Countries. Similarly, the Bidder may obtain insurance services from any eligible country in accordance with Section V Eligible Countries. Prices shall be entered in the following manner:

(a) For Goods:

- (i) the price of the Goods quoted EXW (ex works, ex factory, ex warehouse, ex showroom, or off-the-shelf, as applicable), including GST and other taxes already paid or payable on the components and raw material used in the manufacture or assembly of the Goods;
- (ii) any GST and other taxes which will be payable on

the Goods if the contract is awarded to the Bidder; and

- (iii) the price for inland transportation, insurance, and other local services required to convey the Goods to their final destination (Project Site) specified in the **BDS**.
- (b) **for the Related Services**, other than inland transportation and other services required to convey the Goods to their final destination, whenever such Related Services are specified in the Schedule of Requirements:
- (i) the price of each item comprising the Related Services (inclusive of any applicable taxes).
- (c) bidders may like to ascertain availability of GST exemption benefits, available for contracts financed under World Bank Credits/ Loans. They are solely responsible for obtaining such benefits, which they have considered in their bid and in case of failure to receive such benefits for reasons whatsoever, the Purchaser will not compensate the bidder.

Where the bidder has quoted taking into account such benefits, he must give all information required for issue of necessary Certificates in terms of the Central Excise Notification -108/95 along with his bid in form at S. No. 8 of Section VI. Where the Purchaser issues such Certificates, GST will not be reimbursed separately.

- 14.7 Prices quoted by the Bidder shall be fixed during the Bidder's performance of the Contract and not subject to variation on any account, unless otherwise specified in the **BDS**. A Bid submitted with an adjustable price quotation shall be treated as non responsive and shall be rejected, pursuant to ITB Clause 30. However, if in accordance with the **BDS**, prices quoted by the Bidder shall be subject to adjustment during the performance of the Contract, a bid submitted with a fixed price quotation shall not be rejected, but the price adjustment shall be treated as zero.
- 14.8 If so indicated in ITB Sub-Clause 1.1, bids are being invited for individual contracts (lots) or for any combination of contracts (packages). Prices quoted shall correspond to 100 % of the items specified for each lot and to 100% of the quantities specified for each item of a lot. Bidders wishing to offer any price reduction (discount) for the award of more than one Contract shall specify the applicable price reduction in accordance with ITB Sub-Clause 14.4 provided the bids for all lots are submitted and opened at the same time.

- 15. Currencies of Bid
- 15.1 The Bidder shall quote in Indian Rupees only.
- 16. Documents
 Establishing the
 Eligibility of the
 Bidder
- 16.1 To establish their eligibility in accordance with ITB Clause 4, Bidders shall complete the Bid Submission Form, included in Section IV, Bidding Forms.
- 17. Documents
 Establishing the
 Eligibility of the
 Goods and
 Related
 Services
- 17.1 To establish the eligibility of the Goods and Related Services in accordance with ITB Clause 5, Bidders shall complete the country of origin declarations in the Price Schedule Forms, included in Section IV, Bidding Forms.
- 18. Documents
 Establishing the
 Conformity of
 the Goods and
 Related
 Services
- 18.1 To establish the conformity of the Goods and Related Services to the Bidding Documents, the Bidder shall furnish as part of its Bid the documentary evidence that the Goods conform to the technical specifications and standards specified in Section VI, Schedule of Requirements.
- 18.2 The documentary evidence may be in the form of literature, drawings or data, and shall consist of a detailed item by item description of the essential technical and performance characteristics of the Goods and Related Services, demonstrating substantial responsiveness of the Goods and Related Services to the technical specification, and if applicable, a statement of deviations and exceptions to the provisions of the Schedule of Requirements.
- 18.3 The Bidder shall also furnish a list giving full particulars, including available sources and current prices of spare parts, special tools, etc., necessary for the proper and continuing functioning of the Goods during the period **specified in the BDS** following commencement of the use of the goods by the Purchaser.
- 18.4 Standards for workmanship, process, material, and equipment, as well as references to brand names or catalogue numbers specified by the Purchaser in the Schedule of Requirements, are intended to be descriptive only and not restrictive. The Bidder may offer other standards of quality, brand names, and/or catalogue numbers, provided that it demonstrates, to the Purchaser's satisfaction, that the substitutions ensure substantial equivalence or are superior to those specified in the Schedule of Requirements.

19. Documents Establishing the

19.1 The documentary evidence of the Bidder's qualifications to perform the contract if its bid is accepted shall establish to the

Qualifications of the Bidder

Purchaser's satisfaction:

- (a) (i) that, if required in the BDS, a Bidder that does not manufacture or produce the Goods it offers to supply shall submit the Manufacturer's Authorization using the form included in Section IV, Bidding Forms to demonstrate that it has been duly authorized by the manufacturer or producer of the Goods to supply these Goods in the Purchaser's Country;
 - (ii) Supplies for any particular item in each schedule of the bid should be from one manufacturer only. Bids from agents offering supplies from different manufacturer's for the same item of the schedule in the bid will be treated as non-responsive.
- (b) that the Bidder meets each of the qualification criterion specified in Section III, Evaluation and Qualification Criteria.
- (c) Bids from Joint Ventures are not acceptable

20. Period of Validity of Bids

- 20.1 Bids shall remain valid for the period **specified in the BDS** after the bid submission deadline date prescribed by the Purchaser. A bid valid for a shorter period shall be rejected by the Purchaser as non responsive.
- 20.2 In exceptional circumstances, prior to the expiration of the bid validity period, the Purchaser may request bidders to extend the period of validity of their bids. The request and the responses shall be made in writing. If a Bid Security is requested in accordance with ITB Clause 21, it shall also be extended for a corresponding period. A Bidder may refuse the request without forfeiting its Bid Security. A Bidder granting the request shall not be required or permitted to modify its bid, except as provided in ITB Sub-Clause 20.3.
- 20.3 In the case of fixed price contracts, if the award is delayed by a period exceeding fifty-six (56) days beyond the expiry of the initial bid validity, the Contract price shall be adjusted as by the factor7% for each week or part of week that has elapsed from the expiration of the initial bid validity to the date of notification of award to the successful bidder. Bid evaluation shall be based on the Bid Price without taking into consideration the above correction.

21. Bid Security

21.1 The Bidder shall furnish as part of its bid, a Bid Security, if

required, as specified in the BDS.

- 21.2 The Bid Security shall be in the amount specified in the BDS and denominated in the currency of the Purchaser's Country or a freely convertible currency, and shall:
- (a) at the bidder's option, be in the form of either demand draft, or a bank guarantee from a Nationalised/Scheduled Bank in India.
- (b) be substantially in accordance with one of the forms of Bid Security included in Section IV, Bidding Forms, or other form approved by the Purchaser prior to bid submission;
- (c) be payable promptly upon written demand by the Purchaser in case the conditions listed in ITB Clause 21.5 are invoked;
- (d) be submitted in its original form; copies will not be accepted;
- (e) remain valid for a period of 45 days beyond the validity period of the bids, as extended, if applicable, in accordance with ITB Clause 20.2;
- 21.3 If a Bid Security is required in accordance with ITB Sub-Clause 21.1, any bid not accompanied by a substantially responsive Bid Security in accordance with ITB Sub-Clause 21.1, shall be rejected by the Purchaser as non-responsive.
- 21.4 The Bid Security of unsuccessful Bidders shall be returned as promptly as possible upon the successful Bidder's furnishing of the Performance Security pursuant to ITB Clause 44.
- 21.5 The Bid Security may be forfeited or the Bid Securing Declaration executed:
 - (a) if a Bidder
 - (i) withdraws its bid during the period of bid validity specified by the Bidder on the Bid Submission Form, except as provided in ITB Sub-Clause 20.2; or
 - (i) does not accept the correction of errors in procurement of ITB 31,

or,

(b) if the successful Bidder fails to:

- (i) sign the Contract in accordance with ITB Clause 43:
- (ii) furnish a Performance Security in accordance with ITB Clause 44.

21.6 Not used

21.7 If a bid security is **not required in the BDS**, and

- (a) if a Bidder withdraws its bid during the period of bid validity specified by the Bidder on the Letter of Bid Form, except as provided in ITB 20.2, or
- (b) if the successful Bidder fails to: sign the Contract in accordance with ITB 43; or furnish a performance security in accordance with ITB 44;

the Borrower may, **if provided for in the BDS**, declare the Bidder disqualified to be awarded a contract by the Purchaser for a period of time **as stated in the BDS**.

22. Format and Signing of Bid

- 22.1 The Bidder shall prepare one original of the documents comprising the bid as described in ITB Clause 11 and clearly mark it "ORIGINAL." In addition, the Bidder shall submit copies of the bid, in the number specified in the **BDS** and clearly mark them "COPY." In the event of any discrepancy between the original and the copies, the original shall prevail.
- 22.2 The original and all copies of the bid shall be typed or written in indelible ink and shall be signed by a person duly authorized to sign on behalf of the Bidder. The authorization shall be indicated by written Power of Attorney accompanying the bid.
- 22.3 Any interlineation, erasures, or overwriting shall be valid only if they are signed or initialed by the person signing the Bid.

D. Submission and Opening of Bids

23. Submission, Sealing and Marking of Bids

- 23.1 Bidders may always submit their bids by mail or by hand. When so specified in the **BDS**, bidders shall have the option of submitting their bids electronically.
- (a) Bidders submitting bids by mail or by hand, shall enclose the original and each copy of the Bid, including alternative bids, if permitted in accordance with ITB Clause 13, in separate sealed envelopes, duly marking the envelopes as "ORIGINAL" and "COPY." These envelopes containing the original and the copies shall then be enclosed in one single envelope. The rest of the procedure shall be in accordance with ITB sub-Clauses 23.2

and 23.3.

- (b) Bidders submitting bids electronically shall follow the electronic bid submission procedures specified in the **BDS**.
- 23.2 The inner and outer envelopes shall:
- (a) Bear the name and address of the Bidder;
- (b) be addressed to the Purchaser in accordance with ITB Sub-Clause 24.1;
- (c) bear the specific identification of this bidding process indicated in ITB 1.1 and any additional identification marks as **specified** in the BDS; and
- (d) bear a warning not to open before the time and date for bid opening, in accordance with ITB Sub-Clause 27.1.
- 23.3 If all envelopes are not sealed and marked as required, the Purchaser will assume no responsibility for the misplacement or premature opening of the bid.
- 23.4 Talex, Cable or Facsimile bids will be rejected as non-responsive.

24. Deadline for Submission of Bids

- 24.1 Bids must be received by the Purchaser at the address and no later than the date and time **specified in the BDS**. In the event of the specified date for the submission of Bids being declared a holiday for the Purchaser, the Bids will be received upto the appointed time on the next working day.
- 24.2 The Purchaser may, at its discretion, extend the deadline for the submission of bids by amending the Bidding Documents in accordance with ITB Clause 8, in which case all rights and obligations of the Purchaser and Bidders previously subject to the deadline shall thereafter be subject to the deadline as extended.

25. Late Bids

25.1 The Purchaser shall not consider any bid that arrives after the deadline for submission of bids, in accordance with ITB Clause 24. Any bid received by the Purchaser after the deadline for submission of bids shall be declared late, rejected, and returned unopened to the Bidder.

26. Withdrawal, Substitution,

26.1 A Bidder may withdraw, substitute, or modify its Bid after it has been submitted by sending a written notice in accordance with

and Modification of Bids

ITB Clause 23, duly signed by an authorized representative, and shall include a copy of the authorization (the power of attorney) in accordance with ITB Sub-Clause 22.2, (except that no copies of the withdrawal notice are required). The corresponding substitution or modification of the bid must accompany the respective written notice. All notices must be:

- (a) submitted in accordance with ITB Clauses 22 and 23 (except that withdrawal notices do not require copies), and in addition, the respective envelopes shall be clearly marked "WITHDRAWAL," "SUBSTITUTION," or "MODIFICATION;" and
- (b) received by the Purchaser prior to the deadline prescribed for submission of bids, in accordance with ITB Clause 24.
- 26.2 Bids requested to be withdrawn in accordance with ITB Sub-Clause 26.1 shall be returned unopened to the Bidders.
- 26.3 No bid may be withdrawn, substituted, or modified in the interval between the deadline for submission of bids and the expiration of the period of bid validity specified by the Bidder on the Bid Submission Form or any extension thereof.

27. Bid Opening

- 27.1 The Purchaser shall conduct the bid opening in public at the address, date and time **specified in the BDS.** Any specific electronic bid opening procedures required if electronic bidding is permitted in accordance with ITB Sub-Clause 23.1, shall be as **specified in the BDS.** In the event of the specified date of bid opening being declared a holiday for the Purchaser, the bids will be opened at the appointed time and location on the next working day.
- 27.2 First, envelopes marked "WITHDRAWAL" shall be opened and read out and the envelope with the corresponding bid shall not be opened, but returned to the Bidder. If the withdrawal envelope does not contain a copy of the "power of attorney" confirming the signature as a person duly authorized to sign on behalf of the Bidder, the corresponding bid will not be opened. No bid withdrawal shall be permitted unless the corresponding withdrawal notice contains a valid authorization to request the withdrawal and is read out at bid opening. Next, envelopes marked "SUBSTITUTION" shall be opened and read out and exchanged with the corresponding Bid being substituted, and the substituted Bid shall not be opened, but returned to the Bidder. No Bid substitution shall be permitted unless the corresponding substitution notice contains a valid authorization to request the substitution and is read out at bid opening. Envelopes marked

- "MODIFICATION" shall be opened and read out with the corresponding Bid. No Bid modification shall be permitted unless the corresponding modification notice contains a valid authorization to request the modification and is read out at Bid opening. Only envelopes that are opened and read out at Bid opening shall be considered further.
- 27.3 All other envelopes shall be opened one at a time, reading out: the name of the Bidder and whether there is a modification; the Bid Prices, including any discounts and alternative offers; the presence of a Bid Security, if required; and any other details as the Purchaser may consider appropriate. Only discounts and alternative offers read out at Bid opening shall be considered for evaluation. No Bid shall be rejected at Bid opening except for late bids, in accordance with ITB Sub-Clause 25.1.
- 27.4 The Purchaser shall prepare a record of the Bid opening that shall include, as a minimum: the name of the Bidder and whether there is a withdrawal, substitution, or modification; the Bid Price, per lot if applicable, including any discounts, and alternative offers if they were permitted; and the presence or absence of a Bid Security, if one was required. The Bidders' representatives who are present shall be requested to sign the attendance sheet. A copy of the record shall be distributed to all Bidders who submitted bids in time, and posted online when electronic bidding is permitted.

E. Evaluation and Comparison of Bids

28. Confidentiality

- 28.1 Information relating to the examination, evaluation, comparison, and postqualification of bids, and recommendation of contract award, shall not be disclosed to bidders or any other persons not officially concerned with such process until publication of the Contract Award.
- 28.2 Any effort by a Bidder to influence the Purchaser in the examination, evaluation, comparison, and postqualification of the bids or contract award decisions may result in the rejection of its Bid.
- 28.3 Notwithstanding ITB Sub-Clause 28.2, from the time of bid opening to the time of Contract Award, if any Bidder wishes to contact the Purchaser on any matter related to the bidding process, it should do so in writing.

29. Clarification of Bids

29.1 To assist in the examination, evaluation, comparison and postqualification of the bids, the Purchaser may, at its discretion, ask any Bidder for a clarification of its Bid. Any clarification submitted by a Bidder in respect to its Bid and that changes the substance of the Bidder price of the bid shall not be considered. The Purchaser's request for clarification and the response shall be in writing. No change in the prices or substance of the Bid shall be sought, offered, or permitted, except to confirm the correction of arithmetic errors discovered by the Purchaser in the Evaluation of the bids, in accordance with ITB Clause 31.

30. Responsiveness of Bids

- 30.1 The Purchaser's determination of a bid's responsiveness is to be based on the contents of the bid itself.
- 30.2 A substantially responsive Bid is one that conforms to all the terms, conditions, and specifications of the Bidding Documents without material deviation, reservation, or omission. A material deviation, reservation, or omission is one that:
- (a) affects in any substantial way the scope, quality, or performance of the Goods and Related Services specified in the Contract; or
- (b) limits in any substantial way, inconsistent with the Bidding Documents, the Purchaser's rights or the Bidder's obligations under the Contract; or
- (c) if rectified would unfairly affect the competitive position of other bidders presenting substantially responsive bids.
- 30.3 Bids from Agents, without proper authorization from the manufacturer as per Section XII, shall be treated as non-responsive.
- 30.4 If a bid is not substantially responsive to the Bidding Documents, it shall be rejected by the Purchaser and may not subsequently be made responsive by the Bidder by correction of the material deviation, reservation, or omission.

31. Nonconformities, Errors, and Omissions

- 31.1 Provided that a Bid is substantially responsive, the Purchaser may waive any non-conformities or omissions in the Bid that do not constitute a material deviation.
- 31.2 Provided that a bid is substantially responsive, the Purchaser may request that the Bidder submit the necessary information or documentation, within a reasonable period of time, to rectify nonmaterial nonconformities or omissions in the bid related to documentation requirements. Such omission shall not be related to any aspect of the price of the Bid. Failure of the Bidder to comply with the request may result in the rejection of its Bid.
- 31.3 Provided that the Bid is substantially responsive, the Purchaser

shall correct arithmetical errors on the following basis:

- (a) if there is a discrepancy between the unit price and the line item total that is obtained by multiplying the unit price by the quantity, the unit price shall prevail and the line item total shall be corrected, unless in the opinion of the Purchaser there is an obvious misplacement of the decimal point in the unit price, in which case the line item total as quoted shall govern and the unit price shall be corrected;
- (b) if there is an error in a total corresponding to the addition or subtraction of subtotals, the subtotals shall prevail and the total shall be corrected; and
- (c) if there is a discrepancy between words and figures, the amount in words shall prevail, unless the amount expressed in words is related to an arithmetic error, in which case the amount in figures shall prevail subject to (a) and (b) above.
- 31.4 If the Bidder that submitted the lowest evaluated Bid does not accept the correction of errors, its Bid shall be rejected and the Bid security may be forfeited

32. Preliminary Examination of Bids

- 32.1 The Purchaser shall examine the bids to confirm that all documents and technical documentation requested in ITB Clause 11 have been provided, and to determine the completeness of each document submitted.
- 32.2 The Purchaser shall confirm that the following documents and information have been provided in the Bid. If any of these documents or information is missing, the offer shall be rejected and the bid security may be forfeited.
- (a) Bid Submission Form, in accordance with ITB Sub-Clause 12.1;
- (b) Price Schedules, in accordance with ITB Sub-Clause 12.2;
- (c) Bid Security in accordance with ITB Clause 21, if applicable.

33. Examination of Terms and Conditions; Technical Evaluation

33.1 The Purchaser shall examine the bid to confirm that the Bidder has accepted all terms and conditions specified in GCC and the SCC. without material deviations or reservation. Deviations from or objections or reservations to critical provisions such as those concerning Performance Security (GCC Clause 18). Warranty (GCC Clause 28), Force Majeure (Clause 32), Limitation of liability (GCC Clause 30), Governing law (GCC Clause 9) and Taxes & Duties (GCC Clause 17) will be deemed to be a material

deviation. The Purchaser's determination of a bid's responsiveness is to be based on the contents of the bid itself without recourse to extrinsic evidence.

- 33.2 The Purchaser shall evaluate the technical aspects of the Bid submitted in accordance with ITB Clause 18, to confirm that all requirements specified in Section VI, Schedule of Requirements of the Bidding Documents have been met without any material deviation or reservation.
- 33.3 If, after the examination of the terms and conditions and the technical evaluation, the Purchaser determines that the Bid is not substantially responsive in accordance with ITB Clause 30, it shall reject the Bid.
- 34. Conversion to Single Currency

Not used

35. Domestic Preference

Not used

- 36. Evaluation of Bids
- 36.1 The Purchaser shall evaluate each bid that has been determined, up to this stage of the evaluation, to be substantially responsive.
- 36.2 To evaluate a Bid, the Purchaser shall only use all the factors, methodologies and criteria defined in ITB Clause 36. No other criteria or methodology shall be permitted.
- 36.3 To evaluate a Bid, the Purchaser shall consider the following:
- (a) evaluation will be done for Items or Lots, as **specified in the BDS**; and the Bid Price as quoted in accordance with clause 14;
- (b) price adjustment for correction of arithmetic errors in accordance with ITB Sub-Clause 31.3;
- (c) price adjustment due to discounts offered in accordance with ITB Sub-Clause 14.4;
- (d) adjustments due to the application of the evaluation criteria **specified in the BDS** from amongst those set out in Section III, Evaluation and Qualification Criteria;
- 36.4 The Purchaser's evaluation of a bid will exclude and not take into account.

- (a) In the case of Goods manufactured in India or goods of foreign origin already located in India, GST and other similar taxes, which will be payable on the goods if a contract is awarded to the Bidder;
- (b) any allowance for price adjustment during the period of execution of the contract, if provided in the bid.
- 36.5 The Purchaser's evaluation of a bid may require the consideration of other factors, in addition to the Bid Price quoted in accordance with ITB Clause 14. These factors may be related to the characteristics, performance, and terms and conditions of purchase of the Goods and Related Services. The effect of the factors selected, if any, shall be expressed in monetary terms to facilitate comparison of bids, unless otherwise specified in Section III, Evaluation and Qualification Criteria. The factors, methodologies and criteria to be used shall be as specified in ITB 36.3 (d).
- 36.6 If so **specified in the BDS**, these Bidding Documents shall allow Bidders to quote separate prices for one or more lots, and shall allow the Purchaser to award one or multiple lots to more than one Bidder. The methodology of evaluation to determine the lowest-evaluated lot combinations, is specified in Section III, Evaluation and Qualification Criteria.
- 37. Comparison of Bids
- 37.1 The Purchaser shall compare all substantially responsive bids to determine the lowest-evaluated bid, in accordance with ITB Clause 36.
- 38. Postqualification of the Bidder
- 38.1 The Purchaser shall determine to its satisfaction whether the Bidder that is selected as having submitted the lowest evaluated and substantially responsive bid is qualified to perform the Contract satisfactorily.
- 38.2 The determination shall be based upon an examination of the documentary evidence of the Bidder's qualifications submitted by the Bidder, pursuant to ITB Clause 19.
- 38.3 An affirmative determination shall be a prerequisite for award of the Contract to the Bidder. A negative determination shall result in disqualification of the bid, in which event the Purchaser shall proceed to the next lowest evaluated bid to make a similar determination of that Bidder's capabilities to perform satisfactorily.

- 39. Purchaser's
 Right to Accept
 Any Bid, and to
 Reject Any or
 All Bids
- 39.1 The Purchaser reserves the right to accept or reject any bid, and to annul the bidding process and reject all bids at any time prior to contract award, without thereby incurring any liability to Bidders.

F. Award of Contract

- 40. Award Criteria
- 40.1 The Purchaser shall award the Contract to the Bidder whose offer has been determined to be the lowest evaluated bid and is substantially responsive to the Bidding Documents, provided further that the Bidder is determined to be qualified to perform the Contract satisfactorily.
- 41. Purchaser's
 Right to Vary
 Quantities at
 Time of Award
- 41.1 At the time the Contract is awarded, the Purchaser reserves the right to increase or decrease the quantity of Goods and Related Services originally specified in Section VI, Schedule of Requirements, provided this does not exceed the percentages specified in the BDS, and without any change in the unit prices or other terms and conditions of the bid and the Bidding Documents.
- 42. Notification of Award
- 42.1 Prior to the expiration of the period of bid validity, the Purchaser shall notify the successful Bidder, in writing, that its Bid has been accepted.
- 42.2 Until a formal Contract is prepared and executed, the notification of award shall constitute a binding Contract.

Publication of Award

42.3 The Purchaser shall publish in a www.kmfnandini.coop the results identifying the bid and lot numbers and the following information: (i) name of each Bidder who submitted a Bid; (ii) bid prices as read out at bid opening; (iii) name and evaluated prices of each Bid that was evaluated; (iv) name of bidders whose bids were rejected and the reasons for their rejection; and (v) name of the winning Bidder, and the price it offered, as well as the duration and summary scope of the contract awarded. After publication of the award, unsuccessful bidders may request in writing to the Purchaser for a debriefing seeking explanations on the grounds on which their bids were not selected. The Purchaser shall promptly respond in writing to any unsuccessful Bidder who, after Publication of contract award, requests a debriefing.

Recourse to unsuccessful Bidders

42.4 Upon the successful Bidder's furnishing of the performance security and signing the Contract Form pursuant to ITB Clause 44, the Purchaser will promptly notify each unsuccessful Bidder and will discharge its bid security, pursuant to ITB Clause 21.4.

43. Signing of Contract

- 43.1 Promptly after notification, the Purchaser shall send the successful Bidder the Agreement and the Special Conditions of Contract.
- 43.2 Within twenty-one (21) days of receipt of the Agreement, the successful Bidder shall sign, date, and return it to the Purchaser.

44. Performance Security

- 44.1 Within twenty one (21) days of the receipt of notification of award from the Purchaser, the successful Bidder, if required, shall furnish the Performance Security in accordance with the GCC, using for that purpose the Performance Security Form included in Section IX Contract forms, or another Form acceptable to the Purchaser. The Purchaser shall promptly notify the name of the winning Bidder to each unsuccessful Bidder and discharge the Bid Securities of the unsuccessful bidders pursuant to ITB Sub-Clause 21.4.
- 44.2 Failure of the successful Bidder to submit the above-mentioned Performance Security or sign the Contract shall constitute sufficient grounds for the annulment of the award and forfeiture of the Bid Security. In that event the Purchaser may award the Contract to the next lowest evaluated Bidder, whose offer is substantially responsive and is determined by the Purchaser to be qualified to perform the Contract satisfactorily.

SECTION II - BIDDING DATA SHEET

The following specific data for the goods to be procured shall complement, supplement, or amend the provisions in the Instructions to Bidders (ITB). Whenever there is a conflict, the provisions herein shall prevail over those in ITB.

ITB Clause Reference	A. General
ITB 1.1	The Purchaser is: Hassan District Cooperative Milk Prdoucers' Union Ltd., Hassan
ITB 1.1	The name and identification number of the NCB are: NCB 1-VBMPS-BMCU The number, identification and names of the lots comprising this NCB are: NCB 1-VBMPS-BMCU
ITB 2.1	The Borrower is Government of India
ITB 2.1	The name of the Project is: National Dairy Plan I (National Dairy Support Project).
ITB 4.3	A list of firms debarred from participating in World Bank projects is available at http://www.worldbank.org/debarr

	B. Contents of Bidding Documents	
ITB 7.1	For Clarification of bid purposes only, the Purchaser's address is: Attention: PURCHASE OFFICER Address: Purchase Department, Hassan District Cooperative Milk Producers' Union Ltd., City: Hassan ZIP Code: 573201 Country:India Telephone: +91 08172-240628/240615 Facsimile number:+91 08172-240640 Electronic mail address: Hamul77@yahoo.com	
	C. Preparation of Bids	
ITB 11.1(i)	 The Bidder shall submit the following additional documents in its bid: Bid Submission Form and the applicable Price Schedules, in accordance with ITB Clauses 12, 14, and 15; Tender fees, in cases where tender document downloaded from our website. Bid Security, in accordance with ITB Clause 21, if required; written confirmation authorizing the signatory of the Bid to commit the Bidder, in accordance with ITB Clause 22; Any other supporting document required in the BDS. Documents for Conformity of Goods and related services Supporting Documents against Post Qualification requirement Deviation/Non-Compliance Statement(as per Annexure B) Drawing of BMC Tank whole tank and Drawing of Condensing Unit should be attached for our knowledge purpose. 	
ITB 13.1	Alternative Bids shall not be" considered.	
ITB 14.5	The Incoterms edition is Incoterm 2010.	
ITB 14.6 (a) (iii)	"Final destination (Project Site)":Village Level based Dairy Cooperative Societies(DCS) as per annexure-A	
ITB 14.6 (c)	Bidders may check if any exemption under GST is available or not. PMU, NDDB or EIA would not be responsible for any exemption	

ITB 14.7	The prices quoted by the Bidder "shall not" be adjustable.
ITB 18.3	Period of time the Goods are expected to be functioning (for the purpose of spare parts): 10 years
ITB 19.1 (a)	DELETED
ITB 20.1	The bid validity period shall be 120 days.
ITB 20.3	DELETED
ITB 21.1	(a) Bid Security shall be in the form of DD OR BANK GUARANTEE issued by any Nationalized/Scheduled Bank in India. Bid shall include a Bid Security (issued by bank or surety) included in Section IV Bidding Forms;
ITB 21.2	The amount of the Bid Security shall be: <i>Rs.12 lakhs</i> . It should be in favour of Hassan District Cooperative Milk Producers' Union Ltd., payable at Hassan.
ITB 22.1	In addition to the original of the bid, the number of copies is: One
	D. Submission and Opening of Bids
ITB 23.1	Bidders "shall not" have the option of submitting their bids electronically.
	If bidders shall have the option of submitting their bids electronically, the
ITB 23.1 (b)	electronic bidding submission procedures shall be: <i>Not Applicable</i> .
ITB 23.2 (c)	The inner and outer envelopes shall bear the following additional identification marks: <i>NCB1-VBMPS-BMCU</i>
ITB 24.1	For bid submission purposes, the Purchaser's address is: Attention: PURCHASE OFFICER Address: Purchase Department, HASSAN DISTRICT COOPERATIVE MILK PRODCURS' UNION LTD, ,HASSAN-573201 Floor-Room number: CONFERENCE HALL-2 City: HASSAN ZIP Code: 573201 Country: INDIA The deadline for the submission of bids is: Date: 16.05.2018 Time: 4.00PM
ITB 27.1	The bid opening shall take place at: Street Address: CONFERENCE HALL 2, ADMINISTRATIVE BUILDING, HASSAN DIST. COOP. MILK PRODUCERS UNION LTD, HASSAN-573201 Floor/ Room number: GROUND FLOOR, City: HASSAN Country: INDIA Date: 1 6 . 0 5 . 2 0 1 8 Time: 4.30PM
ITB 27.1	If electronic bid submission is permitted in accordance with ITB sub-clause 23.1, the specific bid opening procedures shall be: <i>Not Applicable</i>

	E. Evaluation and Comparison of Bids	
ITB 36.3(a)	Evaluation will be done for on the basis of total bid price including Taxes.	
ITB 36.3(d)	The adjustments shall be determined using the following criteria, from amongst	
	those set out in Section III, Evaluation and Qualification Criteria:	
	(a) Deviation in Delivery schedule: NO.	
	(b) Deviation in payment schedule: <i>NO</i> .	
ITB 36.4	(a) The purchaser's evaluation of a bid will include all taxes and other charges	
	applicable.	
	(b) No price adjustment should be allowed during the period of execution of	
	contract.	
ITB 36.6	Not Applicable	
	F. Award of Contract	
ITB 41.1	The maximum percentage by which quantities may be increased is: 15%	
	The maximum percentage by which quantities may be decreased is: 15%	

SECTION III. EVALUATION AND QUALIFICATION CRITERIA

Contents

- 1. Evaluation Criteria (ITB 36.3 {d})
- 2. Multiple Contracts (ITB 36.6)
- 3. Postqualification Requirements (ITB 38.2)

1. Evaluation Criteria (ITB 36.3 (d))

The Purchaser's evaluation of a bid may take into account, in addition to the Bid Price quoted in accordance with ITB Clause 14.6, one or more of the following factors as specified in ITB Sub-Clause 36.3(d) and in BDS referring to ITB 36.3(d), using the following criteria and methodologies.

(a) Delivery schedule. (as per Incoterms specified in the BDS)

The Goods specified in the List of Goods are required to be delivered within the acceptable time range (after the earliest and before the final date, both dates inclusive) specified in Section VI, Delivery Schedule. No credit will be given to deliveries before the earliest date, and bids offering delivery after the final date shall be treated as non responsive.

(b) Deviation in payment schedule. [insert one of the following]

No deviation in payment terms is acceptable. Bids with deviation in payment terms shall be treated as non-responsive.

2. Multiple Contracts (ITB 36.6)

The Purchaser shall award the contract to the Bidder that offers the lowest evaluated Price and meets the post-qualification criteria (this Section III, Sub-Section ITB 38.2 Post-Qualification Requirements)

3. Postqualification Requirements (ITB 38.2)

After determining the lowest-evaluated bid in accordance with ITB Sub-Clause 37.1, the Purchaser shall carry out the postqualification of the Bidder in accordance with ITB Clause 38, using only the requirements specified. Requirements not included in the text below shall not be used in the evaluation of the Bidder's qualifications.

(a) Financial Capability

The Bidder shall furnish documentary evidence that it meets the following financial requirement(s):

- The eligible bidders may be those who have an annual turnover not less than Rupees 10 crore or equivalent to Foreign Currency in each of preceding 3 financial years.
- Only Manufacturer will allow to participate against this Tender.
- Joint Ventures will not be allowed.
 - (b) Experience and Technical Capacity

The Bidder shall furnish documentary evidence to demonstrate that it meets the following experience requirement(s):

- Bidder should have already supplied more than 200 BMCs for each year or above capacities for the past three financial years to other Milk Cooperative Union/Federation in India in the same name.
- Bidders shall have an experience in field of BMC business in India since last 5 years.
- (c) The Bidder must furnish details of supplies made by him in the last five years in Performa attached in Section VI along with satisfactory performance certificate issued by the purchaser (compulsory clause) and other supported documents to demonstrate that bidder is meeting Post Qualification requirement.
- (d) The bidder should have a service center with sufficient stock of spare parts in the vicinity of 200 kms from Hassan. Bidder shall provide documentary evidence for the same.

SECTION IV – BIDDING FORMS

Table of Forms

Bidder Information Form	40
Bid Submission Form	41
Price Schedule	
Price and Completion Schedule - Related Services	
Bid Security (Bank Guarantee)	

BIDDER INFORMATION FORM

[The Bidder shall fill in this Form in accordance with the instructions indicated below. No alterations to its format shall be permitted and no substitutions shall be accepted.]

Date: [insert dat	e (as day, n	nonth and	year) of	Bid Si	ıbmission _.
	NCB No.:	[insert nu	mber of	biddin	g process
		Page		of	page

- 1. Bidder's Legal Name [insert Bidder's legal name]
- 2. Bidder's actual or intended Country of Registration: [insert actual or intended Country of Registration]
- 3. Bidder's Year of Registration: [insert Bidder's year of registration]
- 4. Bidder's Legal Address in Country of Registration: [insert Bidder's legal address in country of registration]
- 5. Bidder's Authorized Representative Information

Name: [insert Authorized Representative's name]

Address: [insert Authorized Representative's Address]

Telephone/Fax numbers: [insert Authorized Representative's telephone/fax numbers]

Email Address: [insert Authorized Representative's email address]

6. Attached are copies of original documents of: [check the box(es) of the attached original documents]

Articles of Incorporation or Registration of firm named in 1, above, in accordance with ITB Sub-Clauses 4.1 and 4.2.

In case of government owned entity from the Purchaser's country, documents establishing legal and financial autonomy and compliance with commercial law and not dependent agency of borrower or sub-borrower or purchaser, in accordance with ITB Sub-Clause 4.5.

BID SUBMISSION FORM

[The Bidder shall fill in this Form in accordance with the instructions indicated No alterations to its format shall be permitted and no substitutions shall be accepted.]

Date: [insert date (as day, month and year) of Bid Submission]

NCB No.: [insert number of bidding process]

Invitation for Bid No.: [insert No of IFB]

Alternative No.: [insert identification No if this is a Bid for an alternative]

The guille is a bull of the second of the guille is a bull of the second of the second

To: [insert complete name of Purchaser]

We, the undersigned, declare that:

- (a) We have examined and have no reservations to the Bidding Documents, including Addenda No.: [insert the number and issuing date of each Addenda];
- (b) We offer to supply in conformity with the Bidding Documents and in accordance with the Delivery Schedules specified in the Schedule of Requirements the following Goods and Related Services [insert a brief description of the Goods and Related Services];
- (c) The total price of our Bid, excluding any discounts offered in item (d) below, is: [insert the total bid price in words and figures, indicating the various amounts and the respective currencies];
- (d) The discounts offered and the methodology for their application are:

Discounts. If our bid is accepted, the following discounts shall apply. [Specify in detail each discount offered and the specific item of the Schedule of Requirements to which it applies.]

Methodology of Application of the Discounts. The discounts shall be applied using the following method: [Specify in detail the method that shall be used to apply the discounts];

- (e) Our bid shall be valid for the period of time specified in ITB Sub-Clause 20.1, from the date fixed for the bid submission deadline in accordance with ITB Sub-Clause 24.1, and it shall remain binding upon us and may be accepted at any time before the expiration of that period;
- (f) If our bid is accepted, we commit to obtain a performance security in accordance with ITB Clause 44 and GCC Clause 18 for the due performance of the Contract;
- (g) We, including any subcontractors or suppliers for any part of the contract, have nationality from eligible countries
- (h) We have no conflict of interest in accordance with ITB Sub-Clause 4.3;

(i)	Our firm, its affiliates or su part of the contract—has no country laws or official regu	ot been declared inelig	ible by the Bank, un	nder the Purchaser's			
(j)	The following commissions, to the bidding process or Recipient, its full address, the amount and currency of	execution of the Conhe reason for which ea	ntract: [insert comp ch commission or gr	plete name of each			
	Name of Recipient	Address	Reason	Amount			
	(If none has been paid or is t	o be paid, indicate "nor	ne.")				
(k)	We understand that this bid, together with your written acceptance thereof included in your notification of award, shall constitute a binding contract between us, until a formal contract is prepared and executed.						
(1)	We understand that you are that you may receive.	not bound to accept the	he lowest evaluated	bid or any other bid			
(m)	We hereby certify that we h behalf will engage in bribery	-	are that no person ac	ting for us or on our			
(n)	We undertake that, in compabove contract, we will stri India namely, "Prevention of	ctly observe the laws	against fraud and co	·			
_	ed: [insert signature of persone capacity of [insert legal cap	<u>-</u>	•	Form]			
Nan	ne: [insert complete name of p	erson signing the Bid S	ubmission Form]				
•	v authorized to sign the bid for		-				

Price Schedule Forms

[The Bidder shall fill in these Price Schedule Forms in accordance with the instructions indicated. The list of line items in column 1 of the **Price Schedules** shall coincide with the List of Goods and Related Services specified by the Purchaser in the Schedule of Requirements.]

PRICE SCHEDULE

							Date: NCB No: Alternative No: Page N° of	
1	2	3	4	5	6	7	8	9
Line Item No	Description of Goods	Delivery Date	Quantity and physical unit	Unit price EXW [including GST if any]	Total EXW price per line item [including GST if any] (Col. 4×5)	Price per line item for inland transportation, insurance and other services required to convey the Goods to their final destination and Unloading of Goods	GST payable EXper item if Contract is awarded accordance with ITB 14.6(a)(ii)	Total Price per line item (Col. 6+7+8)
[insert number of the item]	[insert name of Good]	[insert quoted Delivery Date]	[insert number of units to be supplied and name of the physical unit]	[insert EXW unit price]	[insert total EXW price per line item]	[insert the corresponding price per line item]	[insert sales and other taxes payable per line item if Contract is awarded]	[insert total price per item]
1	BMCU as per technical specification attached		50 Number (44-3KL 06-5KL)					
							Total Price for Goods (A)	

Name of Bidder [insert complete name of Bidder] Signature of Bidder [signature of person signing the Bid] Date [insert date]

PRICE AND COMPLETION SCHEDULE - RELATED SERVICES

					Date:NCB No:Alternative No: c	
1	2	3	4	5	6	7
Service N°	Description of Services (excludes inland transportation and other services required in India to convey the goods to their final destination)	Country of Origin	Delivery Date at place of Final destination	Quantity and physical unit	Unit price	Total Price per Service (Col. 5*6)
[insert number of the Service]	[insert name of Services]	[insert country of origin of the Services]	[insert delivery date at place of final destination per Service]	[insert number of units to be supplied and name of the physical unit]	[insert unit price per item]	[insert total price per item]
1	Performance or supervision of the on- site assembly and/or start-up of the supplied Goods Included installation, commissioning, calibration of BMC tank, Lag-locking photos at the time of commissioning. During warrantee period every three month need temperature indicator calibration by master sample and issue certificate to society.			50 Number		
2	Furnishing of detailed operations and maintenance manual in kannada for each appropriate unit of supplied Goods			50 Number		
3	Training of the Purchaser's personnel, at the Supplier's plant and/or on-site, in assembly, start-up, operation, maintenance and/or repair of the supplied Goods			50 Number		
				Taxes		
				Total Price for Related Services (B)		

	Total Bid Price(A+B)	

Name of Bidder [insert complete name of Bidder] Signature of Bidder [signature of person signing the Bid] Date [insert date]

BID SECURITY (BANK GUARANTEE)

[The Bank shall fill in this Bank Guarantee Form in accordance with the instructions indicated.]

[insert Bank's Name, and Address of Issuing Branch or Office]

Beneficiary: [insert name and address of Purchaser]

Date: [insert date]

BID GUARANTEE No.: [insert bid Guarantee number]

We have been informed that [insert name of the Bidder] (hereinafter called "the Bidder") has submitted to you its bid dated [insert date] (hereinafter called "the Bid") for the execution of [insert name of Contract].

Furthermore, we understand that, according to your conditions, bids must be supported by a Bid Guarantee.

At the request of the Bidder, we [insert name of Bank] hereby irrevocably undertake to pay you any sum or sums not exceeding in total an amount of [insert amount in figures expressed in the currency of the Purchaser's Country or the equivalent amount in an international freely convertible currency], [insert amount in words] upon receipt by us of your first demand in writing accompanied by a written statement stating that the Bidder is in breach of its obligation(s) under the bid conditions, because the Bidder:

- (a) has withdrawn its Bid during the period of bid validity specified by the Bidder in the Bid Submission Form; or
- (b) having been notified of the acceptance of its Bid by the Purchaser during the period of bid validity as stated in the Bid Submission Form or extended by the Employer at any time prior to expiration of this period, (i) fails or refuses to execute the Contract, if required, or (ii) fails or refuses to furnish the Performance Security, in accordance with the ITB, and (iii) does not accept the correction of Bid price pursuant to ITB Clause 31.

This Guarantee will expire: (a) if the Bidder is the successful Bidder, upon our receipt of copies of the Contract signed by the Bidder and the Performance Security issued to you upon the instruction of the Bidder; or (b) if the Bidder is not the successful Bidder, upon the earlier of (i) our receipt of a copy of your notification to the Bidder that the Bidder was unsuccessful; or (ii) forty-five days after the expiration of the Bidder's Bid.

Consequently, any demand for payment under this Guarantee must be received by us at the office on or before that date.

This Guarantee is subject to the Uniform Rules for Demand Guarantees, ICC Publication No. 458.

[Signature(s) of authorized bank's representative(s)]

SECTION V. – ELIGIBLE COUNTRIES

Public Information Center

Eligibility for the Provision of Goods, Works and Services in Bank-Financed Procurement

- 1. In accordance with Para 1.8 of the Guidelines: Procurement under IBRD Loans and IDA Credits, dated May 2004, the Bank permits firms and individuals from all countries to offer goods, works and services for Bank-financed projects. As an exception, firms of a Country or goods manufactured in a Country may be excluded if:
- Para 1.8 (a) (i): as a matter of law or official regulation, the Borrower's Country prohibits commercial relations with that Country, provided that the Bank is satisfied that such exclusion does not preclude effective competition for the supply of the Goods or Works required, or
- Para 1.8 (a) (ii): by an Act of Compliance with a Decision of the United Nations Security Council taken under Chapter VII of the Charter of the United Nations, the Borrower's Country prohibits any import of goods from that Country or any payments to persons or entities in that Country.
- 2. For the information of borrowers and bidders, at the present time firms, goods and services from the following countries are excluded from this bidding:¹
 - (a) With reference to paragraph 1.8 (a) (i) of the Guidelines:NIL
- (b) With reference to paragraph 1.8 (a) (ii) of the Guidelines: NIL

PART 2 - SUPPLY REQUIREMENTS

SECTION VI – SCHEDULE OF REQUIREMENTS

1.	LIST OF GOODS AND DELIVERY SCHEDULE	
2.	LIST OF RELATED SERVICES [ITB CLAUSE 14.6(D)] AND COMPLETION SCHEDULE	53
3.	TECHNICAL SPECIFICATIONS	
4.	DRAWINGS(DELETED) ERROR! BOOKMARK NOT DEFINED.	
5.	INSPECTIONS AND TESTS	
6.	PROFORMA OF CERTIFICATE FOR ISSUE BY THE PURCHASER AFTER SUCCESSFUL	. INSTALLATION AND STARTUP OF
TF	HE SUPPLIED GOODS75	
7.	PERFORMA FOR PERFORMANCE STATEMENT	
8.	DECLARATION FOR GST BENEFITS78	

1. LIST OF GOODS AND DELIVERY SCHEDULE

Line	Description of	Quantity	Physical	Final (Site)		Delivery (as per Incoterms) Date			
Item N°	Goods		unit	Destinatio n as specified in BDS	Earliest Delivery Date	Latest Delivery Date	Bidder's offered Delivery date [to be provided by the bidder]	Bid Security in Indian Rupees	
[insert item No]	[insert description of Goods]	[insert quantity of item to be supplied]	[insert physical unit for the quantity]	[insert place of Delivery]	[insert the number of days following the date of effectiveness the Contract]	[insert the number of days following the date of effectiveness the Contract]	[insert the number of days following the date of effectiveness the Contract]		
(1)	BMCU and other accessories as per technical specifications attached	50 (44-3KL 06-5KL)	Number	AS PER ANNEX URE-A	After one month from the date of Purchase Order(PO) release	Within four months from the date of PO Release.		Rs.12 Lakh	

2. List of Related Services [ITB Clause 14.6(b)] and Completion Schedule

Service	Description of Service	Quantity ¹	Physical Unit	Place where Services shall be performed	Final Completion Date(s) of Services
[insert Servic e No]	[insert description of Related Services]	[insert quantity of items to be supplied]	[insert physical unit for the items]	[insert name of the Place]	[insert required Completion Date(s)]
1	BMCU (44-3KL & 6-5KL)	50	Number	As mentioned in Annexure A	Within four months from the date of P.O. release
2	Furnishing of detailed operations and maintenance manual in Kannada for each appropriate unit of supplied Goods	50	Number	As mentioned in Annexure A	Within four months from the date of P.O. release
3	Training of the Purchaser's personnel, at the Supplier's plant and/or on-site, in assembly, start-up, operation, maintenance and/or repair of the supplied Goods	50	Number	As mentioned in Annexure A	Within four months from the date of P.O. release

3. TECHNICAL SPECIFICATIONS

3. Scope of the bidder

• 3.1 Scope

• The bidder's scope start from pump feeding system with balance Tank it shall be pumped to Bulk Milk Cooler. The balance tank shall be of AISI 304 construction, for bulk milk cooler (BMC) of 10000 litres capacity the capacity of tank must be of 200 litres. From BMC, the milk shall be transferred to Road Milk Tanker (RMT) through SS Pipe and milk transfer pump either installed on the RMT or through the pump supplied along with BMC.

Installation & Commissioning

The total job is on turnkey basis and includes supply, unloading at site, installation, testing, commissioning and training of the field personnel. Minor civil works, providing & grouting supports are included in the scope. Moreover, supplier has to demonstrate performance trial runs after commissioning of the unit to the Client. Any other item not mentioned explicitly, but required for proper functioning of the system, has to be provided by the bidder at no additional cost to the client.

Preventive Maintenance

During warranty period supplier will be do preventive maintenance at society level at ones every month of free of cost. Also, if any of the part failed or burnt during warranty period supplier should be provide these spares in free of cost.

Service during warranty period

During warranty period, if any complaint will come from Village Level Cooperative Societies(VDCS) for BMC. The complaint must be attended <u>within 12</u> hours. If any component are burnt ,supplier should be replace that components within 24 hours.

Training

Supplier will give training of BMC to society level BMC Operator at the time of commissioning (two time of Milk collection). If training require by society secretary or operator , training arrangement should be done by supplier in group by the free of cost.

Service-centre (store)

Service centre shall be established in Hassan District, so that complaints can be easily resolved within 12 hours & spares easily provided within 24 hours. If any component of BMC require, the component should be easily available in store.

<u>Calibration</u> Calibration of the BMC tank must be done by supplier at the time of BMC Commissioning and also provide the lag-locking photographs after satisfied calibration. Also supplier have to give calibration certificate of temperature indicator quarterly during warrenty period.

DIRECT EXPANSION TYPE BULK MILK COOLING SYSTEM (more than 2000 L capacity)

SPECIFICATION NO. 01.13.005.00 R1 (2009)

1. General Description

Design, supply, installation, testing and commissioning of Direct Expansion type bulk milk cooling systems including all accessories & items given in the detailed scope of supply, on turnkey basis.

2. Functional Requirement

These systems would be installed in village Dairy Co-operative Society (DCS)/ village milk collection centre, which collects milk everyday in the morning & evening from milk producers. The milk collected shall be stored in the bulk milk cooler and cooled from ambient temperature to 4^0 centigrade. The stored milk shall be dispatched to dairy plant through insulated road milk tanker once in a day.

3. Design Requirement

3.1 Capacity

The net capacity of the bulk milk cooler shall be as mentioned above and as per the requirement given in the enquiry/tender document. However, the gross capacity in all the sizes shall be around 10% higher than the rated capacity to avoid accidental spillage of milk due to agitation or any other reason.

3.2 Applicable manufacturing/ design code

3.2.1 Bulk Milk Cooler (BMC)

The BMC tank shall meet the requirements of **ISO 5708 – 2 II (Latest version**) for milk collection cycle of two times in a day with not more than 3.0 hours cooling time from 35 to 4 Deg. C for all milking* and not more than 1.5 hours for second milking* i.e. from 10 to 4 Deg. C.

For design of condensing unit for BMC **ARI Standard 520-2004** (Air-Conditioning & Refrigeration Institute, Arlington, Virginia) for ambient temperature condition shall be applicable.

The tank shall be of an established & proven Direct Expansion type design, in regular production & use and not a prototype.

(*Note: All milking means quantity of milk received in either morning shift or evening shift. When a Tank for two milkings is either empty or contains 50% of its' rated volume of milk at 4^0 C, and 50% of the rated volume of milk at 35^0 C is added in one batch, all of the milk shall be cooled to 4^0 C in not more than the specified cooling time.

If a volume of milk corresponding to the second milking is added to the tank, the total volume of the milk shall be cooled to 4° C in not more than specified cooling time.)

3.2.2 Refrigeration System

The refrigeration system shall be designed to meet performance ratings of positive displacement condensing units specified in **ARI Standard 520- 2004.**

3.2.3 Accessories

Accessories like diesel generator set, electric & control cables, control panel, temperature sensor, electrical switchgears, refrigeration control valves & fittings etc. shall be of approved make as detailed in the specifications and shall meet the requirement of the latest relevant **Indian electricity rules,** ISO/BIS Standards.

4. Scope of the bidder

4.1 Scope

The bidder's scope starts from receipt of milk in milk can with SS 304 funnel with SS mesh and then manual pouring in to a balance tank (200 litres) and pumping to bulk milk cooler. Alternatively, a 50 litres balance tank with an outlet valve will be placed on a weighing machine (weigh machine not included in scope) platform from which milk will be discharged into the 200 litres balance tank. In some cases, the reception equipment will include a can tipping bar. The balance tank of capacity 200 litres shall be made up of SS sheet conforming to AISI 304. From BMC, the milk shall be transferred to Road Milk Tanker (RMT) through food grade quality flexible hose of adequate length and milk transfer pump installed either on the RMT or through the pump supplied along with BMC.

Bidders should furnish separate prices for gravity fed system as well as for pumped system.

4.2 Supply

The bulk milk cooler shall be a complete unit with the refrigeration system, agitator(s), lockable inlet & outlet valve with strainer. Also includes supply of AISI 304 balance tank with SS 304 filter for pumped system, SS piping & milk hose of food grade quality, unions and milk transfer pump of 5000 LPH, SS 304 pipes & fittings, erection materials, pipe supports, floor plates, hinged type pipe clamps. The hose pipe shall be 10 metres long and end with SS liner and blank nut chained with the hose. A wall mounted SS hook of adequate size for hanging the milk hose pipe roll shall also be provided. The scope includes electrical & control panels and interconnecting cables, cable conduits shall also be supplied, earth pit pipes with removable cover & earthing as required by local electrical regulation.

The indicative distances between BMC outlet to milk pump inlet - 3 m, BMC to Mains power point & DG set - 20 m may be considered for calculating cable, SS piping requirement, supports etc. However, the exact distances shall be as per site conditions and complete piping & cabling necessary for installation shall be supplied.

4.3 Installation & Commissioning

The total job is on turnkey basis and includes supply, installation, testing, commissioning and training of the field personnel. Minor civil works, providing & grouting supports are included in the scope. Giving satisfactory training to the staff

of the collection centre and trial runs for the complete unit. Moreover, supplier has to demonstrate performance of the unit as per operating parameters to the Client /NDDB.

5. Constructional Features

5.1 Bulk Milk Cooling Tank

5.1.1 Material of construction

Complete tank inner, outer, evaporator bottom including the accessories, as under, shall be fabricated from Stainless Steel AISI 304 material.

Piping & fittings, Filter, Lockable cover, Agitator shaft & blade. Adjustable ball feet with 50 mm height adjustment, Dipstick, Outlet & Inlet valves, blank flanges, ladder & manhole of about 45 centimeters diameter, Air Vent etc. for closed type milk cooling tank.

The filter screen shall be fine wire mesh. All the gaskets shall be of food grade nitrile or neoprene rubber material. The AISI 304/316 evaporator shall be dimpled pressed plate jacket put as bottom plate of the inner tank. The bottom evaporation surface in contact with milk as well as outer SS cladding is passivated by standard chemical treatment to impart corrosion resistance.

5.1.2 Shape & Orientation

The BMCs greater than 2000 lit capacity, shall be closed type horizontal circular/elliptical cross sectional shape with top man hole. The shape of the BMC tank shall conform to international sanitary design.

5.1.3 Milk Cooler Tank & Evaporator

The AISI 304 tank for the bulk milk cooler should be either in circular or elliptical orientation, which imparts smooth distribution of the fat in milk when agitator is set in to operation.

The tank shall be so designed that all surfaces in contact with milk are readily accessible either in their position or after dismantling to permit thorough cleaning.

Inner Vessel:

All joints shall be TIG welded, any filler rod used being suitable for the parent metal. All welds shall be ground smooth and free from crevices, porosity and brittleness. All milk contact metallic surfaces of the inner vessel and its attachments should have finish not less than 150 grit finish.

Any permanent attachment to the inner vessel shall be welded with fillet radii not less than 6 mm.

All parts of the inner vessel shall drain directly to the outlet.

Internal corners formed round the bottom of the inner vessel and outlet well shall be of not less than 25 mm in radius. Other internal corners shall be not less than 15 mm in radius.

The bottom dimpled jacket for refrigerant flow is to be fabricated through laser welding technology. In cylindrical/ elliptical tank the jacket shall be at least up to 1/3 height of the tank. In case of double compressor, total evaporator area shall be divided and separated into two sections. Each section shall have separate suction & discharge connecting to each compressor. The evaporator surface in contact with the milk should be passivated by standard treatment to impart corrosion resistance.

5.1.4 Tank Fittings & accessories

The tank shall be provided with **stainless steel inlet with special "no-foam" design**, outlet 38/51 mm butterfly valve & blank union with locking arrangement, SS spray balls, a sampling cock lockable type at outlet before butterfly valve, manhole and cover with locking arrangement, agitator etc.

At the bottom of the outlet cup on the outer surface, a temperature sensor shall be permanently fixed. It shall sense the temperature of the surface at the outlet and transmit the signal to the digital indicator. The digital type temperature indicator shall be provided in the control panel with back up battery.

The tank shall be provided with SS calibrated dipstick to measure the volume of milk inside the tank. The dipstick shall be graduated from 10% or less to not less than 100% of the rated volume. Each division on dipstick shall represent a volume not greater than 0.5% of the rated volume. The calibration chart of dipstick having adequately bold letters shall be laminated/ framed and shall be supplied with BMC. The tank shall be equipped with agitator(s) capable of producing a uniform distribution of fat in the milk.

All SS fittings shall be of SMS standard.

The BMC shall be provided with 1 (one) AISI-304 filters with SS fine wire mesh suitable to filter extraneous matter such as dust particles, hay, flies, cow dung pieces / particles etc. The filter shall be designed and installed in such a way that it can frequently and easily be cleaned.

The approach ladder for manhole cover shall be an in-built feature of the unit. The tank shall be provided with AISI 304 adjustable ball feet tamper proof type having provision of 50 mm height adjustment. Provision of a bolt for earthing connection may be provided on one of the legs. Number of ball feet shall be minimum 4 for small capacity tank and 6 for bigger tank.

5.1.5 Balance Tank, Capacity 200 Litres

The balance tank of 200 litre capacity shall be of sanitary design, fabricated from SS 304 sheet of 1.6 mm thick for shell & 2 mm bottom. Outlet S S Cup and sufficient slope shall be provided at bottom of tank for complete draining of milk.

The dimension of tank and fittings shall be suitable to meet milk collection operations at centre. I no SS removable cover (1.0 mm thick) shall be provided. S S filter made from 1.6 mm S S plate with 2 mm dia holes (Removable type) to be provided for placement in the balance tank to remove coarse suspended impurities from milk. Four number Ball feet shall be provided for height adjustment of 50 mm. All fabricated parts shall be polished neat to 150 grit.

5.1.6 Stainless Steel Sanitary Milk Pump

5 KLPH, 10 MWC capacity milk pump shall be supplied for pumping milk from balance tank to BMC and BMC to road milk tanker. Pump impeller & casing shall be made out of SS AISI 304/316 material. All milk contact surfaces shall be finished to minimum 150 grits. The pump should be of sanitary design. Inlet & outlet of the pump shall have ends with SMS union. The pump shall be provided with approved make motor having `E'/'F class insulation and IP 55 protection. The flanged end motor shall have stainless steel shaft having hygienic mechanical sealing arrangement to prevent leakage from pump casing to rotor side of the motor. Pump shall have SS shroud with air ventilation grill for circulating cooling air. The pump shall have SS adjustable ball feet.

5.1.7 Insulation

The insulation of the tank shall be done by injection, in situ, of high density (minimum 40 kg/m3, Chlorofluorocarbon free and environmental friendly) polyurethane foam without having any imperfection and hygroscopicity. The efficiency of insulation should be such that at max 50° C ambient temperature the rate of rise of the mean temperature of the milk shall not exceed by 1° C in four hours, when the rated milk volume initially at about 4° C is allowed to stand undisturbed as per the requirement of ISO 5708 2 II when the refrigeration unit is not working.

5.1.8 Cleaning In Place (CIP)

For closed type tank configuration, facilities for Cleaning- In- Place shall be provided which shall include CIP spray balls and piping from milk reception/balance tank through milk transfer pump to bulk milk cooler.

5.1.9 Welding & Finishing

Inner, outer, intermediate dimpled jacket and nozzle connections shall be welded with TIG process only. The inner shell and all other product contact surface shall be polished up to minimum 150 grit finish. The outer surface to be polished with 150 grit dull finish or a circle finish.

5.2 Refrigeration System

The refrigeration system shall be designed to comply with **ARI Standard 520-2004** and to meet the requirements of milk collection system of ISO 5708, Class 2 II. The refrigeration system shall be of direct expansion type, with Freon-22 (R-22) or CFC free environmental friendly refrigerant to cool the raw milk from reception temperature to 4° C in the prescribed period mentioned. The evaporator(s) of the refrigeration system shall form a part of the milk tank body as dimpled jacket in the

inner shell bottom at least up to $1/3^{rd}$ height of the circular/elliptical (closed) tank. It would be better in case the system is compatible for the refrigerant R 407 C.

The refrigeration system shall be direct expansion type to perform cooling function in an ambient temperature of 46 0 C with air-cooled condenser.

5.2.1 Compressor

The refrigeration compressor shall be adequate enough to ensure that milk is cooled to 4^0C in the prescribed time limit and suitable to operate at 0^0C suction temperature and 60^0C condensing temperature (air-cooled condenser) assuming 46^0 C ambient temperature.

The refrigeration compressor (s) shall be rotary/ reciprocating, hermetically sealed type essentially suitable for refrigeration application in hot & humid Indian climatic conditions. The motor of the compressor should have a thermistor temperature sensor embedded in windings for protection from excessive heating due to overloading or short-circuiting. Similarly, a protection against off cycle migration of refrigerant to the compressor is necessary in the refrigeration unit, preferably a self-regulating PTC crank case heater. The compressors selected should be energy efficient and consume least power to meet the cooling load requirements.

For the bulk milk coolers at least two refrigeration compressors system shall be provided.

The complete system shall work on three phase mains supply.

Client shall approve Make(s) of the compressor.

Bidders can also offer Energy Efficient Hermetically Sealed Scroll Compressors of as alternative to rotary / reciprocating compressors.

5.2.2 Condenser

The condenser shall be air cooled finned tube type having sufficient heat transfer area designed for extremely high ambient temperature given above. The air circulation fan of condenser shall preferably be induced draft type sucking cold air over the compressors and throwing hot air out of the premises/place of installation. The condensing temperature should not be less than 60° C considering operating ambient temperature of 46° C.

5.2.3 Receiver

For refrigeration circuit a suitable size liquid receiver mounted on the skid near compressor to assist system to store refrigerant during pump down cycle as well as incase of maintenance.

5.2.4 Thermostatic Expansion Valve

Suitable size and capacity Thermostatic expansion valve should be provided in the refrigeration circuit of the bulk milk cooler. The TX valve should be Maximum Operating Pressure type and of adequate capacity to feed optimum quantity of refrigerant to the milk cooling tank evaporator.

5.2.5 Refrigerant pipe, fittings & controls

All pipes, valves, fittings & controls shall comply with the latest relevant BIS code applicable. Isolation valves at suction & discharge sides of the compressors is provided for compressor isolation, during maintenance of the system. A suction pressure regulating valve (KVL) shall be provided to restrict suction pressure with in a reasonable limit for preventing tripping of compressor. Copper/SS tubing shall be routed in such a way that if any leakage occurred during operation can easily be detected and the defective portion can be repaired/ replaced without dismantling the whole system. All the pipes shall be clamped properly with fixed support. In case of double compressor system, pipe, fitting & control should be designed in such a way that both the compressors can run independently. The tubing shall be insulated wherever necessary.

6. Electrical Control Panel

6.1 Control Panel

Four control panels shall be provided, one for the main power supply tapping, second for the refrigeration unit, the third for the milk tank and fourth for lighting, testing equipment and computers etc. Each panel shall be provided with suitable switchgear of required ratings for switching and protection as per the system requirement. The incoming and outgoing power supply terminals shall be covered and secured with a lead seal to prevent tampering. The door of the panels should be provided with lockable handles.

6.1.1 Main Control Panel with Automatic Voltage Stabilizer

This should be suitable to receive the incoming State Electricity Authority grid supply as well as supply from BMCs D G Set . Grid supply to be stablised for voltage fluctuation by a automatic type voltage stabliser. Output electric supply either stablised grid supply or DG Set supply, to be selected through a change over switch. Provision to be made in this control panel to feed output supply to the refrigeration unit & BMC agitators through refrigeration control panel, to milk dispatch pump & to lighting Distribution board.

D G set & stabliser are to be of three phase.

This panel is to be of rating **25 KVA three phase** for 5 KL BMC.

For 25 KVA 3 phase Automatic stabliser, following major components shall be provided:

- (1) The incoming grid power (Phase voltage 180 to 280 volts) shall be given through TPN MCB of suitable rating. Relay system to be provided to ensure that if incoming voltage is either less than 180 volts or more than 280 volts in any phase, stabliser stops incoming power to stabliser for it's safety
 - (2) LED type Indicator lamps (R, Y, B) on the individual phases of supply.
 - (3) A bypass switch of suitable rating for by passing correcting transformer
 - (4) Correcting transformer ,air cooled type, for each phase, with 6 steps each of 20 volts (phase 180-200-220-240-260-280 V) to be controlled through a relay system or servo controlled .
 - (5) A Change-Over TPN switch of suitable rating between DG Set and corrected mains

Power supply

- (6) A digital input and output (corrected) voltage /current/frequency indicator with selector Switch for all three phases. The indicator shall be so provided as to be visible from a distance of at least 5 metre, and so located as to requiring no special effort to see the readings.
- (7) TPN MCB of suitable rating for correcting transformer ON/ OFF
- (8) TPN MCB of suitable rating for supplying power to Refrigeration Panel .
- (9) TPN MCB of suitable rating for supplying power to lighting DB
- (10) TPN MCB of suitable rating for supplying power to starter of milk pump. Paralley 20 A metallic power plug socket to be provided.
- (11) If the corrected voltage at the output side goes beyond 180-280 volt range, a control relay/power contactor combination shall cut off output power supply with a loud alarm.
- (12) Suitable terminal blocks, heavy duty ,4 way for incoming mains (of suitable rating)and
- 4 way (of suitable rating) for DG Set incoming and the terminal blocks (4 way of suitable rating for refrigeration, 4 way 32 A for lighting DB, 4 way of suitable rating for milk pump)
 - heavy duty for outputs.
 - (13) Housing enclosure of powder coated MS of appropriate size
 - (14) Double compression heavy duty Brass cable glands for two incoming armored cables & PVC cable.

6.1.2 Refrigeration Control Panel

The refrigeration unit shall be provided with a control panel made out of Stainless Steel suitable for wall mounting near the unit. The panel shall be provided with motor starters, ON/OFF push buttons & necessary MCBs, control wiring, line voltage controller to guard the compressor against the supply voltage fluctuations. In case more than one compressor is provided in the refrigeration system, the control panel shall be provided with a sequence controller & timer to start one compressor at a time to avoid power supply surge. The panel shall also have facility to operate refrigeration unit on auto/ manual mode. In the auto mode, as soon as the milk temperature reaches to pre-set value, the compressor should be switched off to avoid freezing of milk.

6.1.3 Milk Tank Control Panel

The milk tank shall be provided with a wall mounted control panel with timer to control the intermittent operation of the agitators & a digital temperature indicator to indicate the milk temperature to one decimal place with least count of $0.1^0\,$ C on continuous basis. It shall include suitable switchgears etc as required for switching & protection. Panel shall have provision for pre setting temperature (but not below 4 deg C) of BMC Tank for starting/stopping refrigeration compressors. Suitable battery back up to is be provided so that temperature can be indicated when there is no electric supply.

6.1.4 Domestic Power Distribution Board

This distribution board would get single phase power from grid supply directly (it is assumed that when grid power is received in this DB, Main control panel gets power only from D G Set) as well as stabilized power from main control panel and feed power for lighting, electric geyser/solar water heating system, testing equipment/computers. The main components of this DB shall be as follow:

- 1) Wall mounted distribution board, MCB type
- 2) 32 DP Change over switch
- 3) 32 A DP MCB as incoming
- 4) 3 nos. 10 A MCB SP for lighting
- 5) 3 nos. 20 A MCB SP for geyser/Solar water heater, AMCU etc.

6.1.5 Cables & Electrical Switch gears

All electrical switchgears and controls required for the complete system shall be of suitable rating.

All permanent wiring installed on the tank or associated units shall be carried out using PVC cable in heavy gauge, screwed galvanized steel conduit or plastic conduit, or in mineral-insulated copper-sheathed cable.

Flexible electrical connections shall be made only to items normally movable in service. Such flexibles shall be PVC insulated copper conductor cable not less than 24/0.20 mm in size (see IS 694 (Part1-1964*) and earth continuity conductors of PVC insulated copper conductor shall be provided. Cable between DG Set and main panel shall be either steel armoured or un-armoured in steel conduits. For all electrical cables, suitable water tight cable glands and lugs should be used at ends.

6.1.6 Earthing

The earthing should be carried as per IS:3043 - 1987 (reaffirmed 2001) - "Code of practice for earthing". Pipe type earthing can be used. The chassis, framework and the fixed parts of the metal casing of the tanks, D G Set body, refrigeration plant skid, and all panels shall be provided with two separate earthing terminals. Neutral of D G Set shall be earthed by a separate independent earth pit. Neutral of Grid supply shall also be earthed by a separate independent earth pit Suitable G I Strip(minimum 25x3 mm) to be used for connecting earth pit with nearest equipment earthing point. From this point earthing to other points can be looped by suitable GI Strip or PVC insulated copper conductor cable of green colour (size minimum 1x 4 Sq mm)

In view of above, total four earth pits to be provided for each installation.

The earthing terminals shall be readily accessible and so placed that the earth connections of the equipment are maintained when the cover or any other movable part of equipment is removed.

^{*} Specification for PVC insulated cables (for voltage up to 1100V): Part 1 with copper conductor (revised).

The earthing terminal shall be identified by means of the $' \equiv '$ marked in a legible and indelible manner on or adjacent to the terminals.

7. Diesel Generator Set (Air/ water- coolant cooled) and accessories:

The DG set shall be for three phase generation. Proper justification with calculations should be provided for capacity of the diesel engine and alternator being considered for DG set.

The engine should be rated for continuous operation for:

The refrigeration system, milk tank agitator & milk- loading/ unloading pump, hot water geyser (approx. 2 Kw), AMCU, Lightings, ceiling fan.

Rated maximum output of the DG set should be calculated considering the load
mentioned, over and above 10 % additional load shall be considered to handle any
eventuality and with the ambient design dry bulb (DB) temperature (summer)
Deg. C, and winter Deg. C.

Performance Requirement: The working KVA rating at site conditions after accounting for de-rating as per IS: 10001/10002 or equivalent shall be obtained at 0.8 power factor.

The Genset should have the engine, alternator, control panel and silencer as an integral part of the unit. The major components of the DG set shall comprise:

7.1 Diesel Engine: The diesel engine should be suitable for Power Generation application type air /water cooled and capable of developing required BHP when running at 1500 rpm under NTP conditions and not agricultural engine. The engine should be built to IS 10000/ISO 3046/BS 5514/649 and rated for continuous running of 24 hours with an overload capacity of 10 % for a period not exceeding 1 hour in any 12 hours running. Diesel engine up to 20 KW should have valid BIS license and certificate clearly mentioning use for 'General purpose ' application as per IS 10001 norms. Engine ratings should be for operation at full load condition and should be suitable to take 100% block load.

The engine instrument panel shall be supplied with:

- Ignition key
- Starting push button
- Lubricating oil pressure gauge
- Temperature gauge for cooling water

- Temperature gauge for lubricating oil
- RPM meter (Analog type)
- Battery charging ammeter
- **7.1.1** The diesel engine should be four stroke, naturally aspirated/ turbocharged, Multi Cylinders & complete with the following:
- a) Flywheel & flywheel housing
- Engine Air/water cooling system with cooling fan & radiator CAC coolant with recovery bottle
- c) Air intake, fuel and lubricating oil filters
- d) Oil bath air cleaner
- e) Standard day fuel tank having capacity suitable for minimum 8

hours continuous operation. The **tank** shall be made with steel sheet of minimum thickness 18 gauge and complete with standard accessories such as drain pipe, fuel level indicator, valves, lockable cover, low-level contact & alarm. This tank to be inside the acoustic enclosure.

- f) Fuel pump with mechanical governor
- g) Coupling
- h) Exhaust silencer residential type.
- Holding down bolts, MS combination base frame & AVM pads.
- j) Self-starting arrangement with 12V suitable rated heavy-duty Lead Acid accumulator type battery with

- Solid-state battery charging arrangement and cables.
- k) Standard set of tools.
- I) First fill of Lubricating oil
- m) First fill of coolant
- n) Lubricating oil pressure & temp. gauge
- control panel for engine with engine safety against over speed, High water & cylinder liner temperature, V-belt failure, low lubricating oil pressure, low water level in radiator auxiliary failure, air cleaner choke indicator.
- p) One brand new oil barrel of 200 litre capacity with manually driven gear/barrel pump for diesel transfer along with reinforced PVC hose for supply.
- **7.2 Alternator:** The engine should be closely / flexible coupled to suitable self excited, self regulated (through an AVR) alternator developing required KVA at 0.8 power factor, 3 phase, 50 cycle/sec, 415 volts AC power supply under NTP conditions when running at 1500 RPM. The alternator should be brushless type, screen protected and fitted with end shield and ball roller bearings. The alternator shall have 'H' class of insulation. It shall conform to IS 13364 (Part 1) 1992 up to 20 KVA or IS 13364 (part II) 1992 above 20 KVA or IS 4722 of 1992.
- **7.3 Control Panel:** The diesel generating set should be supplied with suitable floor/wall mounting type control panel duly pre-wired with the following instruments:

One suitable scaled and rating KwHr meter with accessories
One ammeter with selector switch
One voltmeter with selector switch
One no. frequency meter
One no. hour meter (time totalizer)
One set of epoxy resin casted CTs
of suitable ratings
One suitable capacity MCCB with
overload and short circuit
protection to disconnect power
supply in case load of generating
set increases beyond permitted

limits. The rupturing capacity of the MCCB should not be less than 35 KA.

One set of TPN Bus bars insulated with heat shrinkable PVC sleeves (maximum permissible current density shall be 0.8 amps / mm²) One set of indicating lamps and control fuses

The control panel should conform to the Indian electricity rules.

- **7.4 Frame:** The diesel engine and alternator should be mounted on specially designed combination base plate and MS structure of extremely rigid fabrication. The base plate should be suitable for mounting the set on AVM pads over the foundation.
- **7.5 Acoustic Enclosure:** DG set should carry a valid approval certificate issued as per CPCB norms complying with the provision of the Environment (Protection)

second Amendment Rules 2002, vide notification no G. S. R. 371 (E), dated 17th May 2002 & amended by GSR 448 (E) dt.12/07/2004. The Diesel Generator sets shall have a standard acoustic enclosure of 25 dB (A) insertion loss. The exhaust pipe with exhaust muffler with insertion loss of minimum 25 dB (A) is connected to the exhaust manifold preferably with flexible bellows.

7.5.1 General requirement: The enclosure could be tailor made suitable for both indoor and outdoor installation as per the requirement and depending upon the capacity of D.G. Set. The enclosure should be aesthetically designed to perform for optimum noise attenuation and in no way derate the performance of the DG set in extreme summer conditions. Acoustic Enclosure should be Environment Friendly and protected against rodents etc. The enclosure should have:

Adequate ventilation for genset cooling air requirement.

Absorbent /insulating material used is fire radiant.

Suitable thermal lagging to avoid localized heating of adjoining part of exhaust.

Appropriately located control panel.

Easy access side doors to service points on gensets.

Doors fitted with high quality Gaskets to avoid leakage of sound.

Provision for Engine Air Filters to suck the Fresh Inlet Air for Engine directly from atmosphere

Sufficient space inside to fit different accessories like batteries, etc & the maintenance can be done inside with the easy movement of the working person on DG Set.

Enough space for Control Panel and Fuel Tank inside Enclosure

For the proper ventilation and to maintain the temperature inside the enclosure Forced ventilated Air Circulation System using Axial Flow Fan(s) to meet total engine requirements & air charges should be provided. (Air volume required for ventilation is to be based on the combustion, cooling air, & alternator cooling air as per the specifications given by the engine and alternator

manufacturer.) Temperature of enclosure should not exceed beyond 5^0 C of ambient temperature.

7.5.2 Constructional features of acoustic enclosure:

The construction and design of the Acoustic enclosure shall be very rugged, durable and shall be virtually maintenance free.

The acoustic panels shall be filled with a special grade high-density mineral wool retained on the inside by perforated GI sheets specially designed for optimum sound attenuation.

The outer surface of the Acoustic Panels shall be fabricated of preformed 16G corrugated CRCA sheet steel of a SAIL make only. All sheet steel frames shall be of 16G CRCA sheets of SAIL make only.

All structural members such as angles / channels used in the construction of the enclosure frame shall of TISCO / SAIL make only.

All materials used for Acoustic Enclosure shall be fire resistant /fire retardant grade.

The sheet steel treatment shall consist of degreasing, de-rusting and phosphating followed by two coats of zinc chromate primer, followed by two coats of Zinc - pholite surface for superior corrosion resistance and two coats of finish paint.

For effective Acoustic sealing, necessary gasketing material shall be provided. All hardware and fittings used shall be passivated with zinc.

7.5.3 In case the DG Set is installed indoor, the exhaust should be taken outside the building. The exhaust pipe of engine should be extending horizontally out of the building (assumed minimum length of pipe 3 meters, then upward rise two meters and terminate with a weather protection cowl). The entire pipe length should be insulated with resin-bonded mineral wool with aluminum cladding.

All the necessary supports are to be provided for sturdy installation.

8. Water for cleaning at milk collection centre

8.1 **Water storage** (This tank shall be included only if water heating other than Solar Heating has been adopted. For solar heater a tank has been included in the specification as per Clause No. 8.2.3):

A 1000 litre capacity overhead water storage tank - ISI Mark Rotational molded Polyethylene Water Storage Tank (HDPE heavy duty), hygienic construction conforming to IS: 12701/96 closed type with manhole for maintenance. The tank to be provided with float valve, drain, & overflow and other standard accessories. The tank stand assembly shall be made of MS angle of size 35x35x5 mm duly pre-treated and hot dip galvanized after fabrication. If during erection at site the zinc coating is punctured due to welding or any other reason, the punctured portion shall be painted (at least 2 coats) with silver paint. Alternatively tubular structure with powder coating could also be provided. GI B class piping up to convenient points in the room for hot and cold water supply shall be supplied & connected in consultation with client.

The piping from the mains water source up to the water storage tank shall be provided by client.

8.2 Solar Water heating system:

Solar Water heating system, indirect type, rated capacity **200 LPD**, shall be used for cleaning of BMC tank and other equipment, piping etc. at milk collection centre. System to be designed considering that ambient temperature normally does not go below 3 Degree C & normally Sun heat is available for minimum 6 hours and cold water having hardness not more than 1000 ppm. Hot water to be made available at maximum 70 Degree C. Capacity to be derived considering delta T as 50 degree C in 6 hours. The system shall consist of solar flat plate collector(s), collector stand assembly, stainless steel insulated hot water storage tank with heating jacket and various other components as per detailed specification given below.

8.2.1 Solar Flat Plate Collector:

Solar flat plate collectors shall conform to IS: 12933 (part 1) with amendment up to date and IS: 12933 (Part 2)/ 2003 with amendment up to date and various components shall be as under:

(a) Cover Plate: Cover plate shall be toughened glass and thickness of minimum 4 mm conforming to IS: 12933 (Part 2)/ 2003. The solar transmittance of the cover plate shall be minimum 82% at near normal incidence.

(b) Collector Box: Collector box frame shall be made of Extruded Aluminium sections only. Type, grade, size, workmanship and finish of the material used shall be as per IS: 12933 (Part 2)/ 2003. The minimum thickness of aluminium shall be as under:

Channel section for sides : 1.6 mm

Sheet for bottom : 0.7 mm Support for glass retaining : 1.2 mm

(c) Absorber: Absorber shall consist of riser, header and sheet for absorber. The thickness of header and riser tube shall be minimum 0.71 mm and 0.55 mm respectively, and made up of copper only. The diameter of header & riser tube shall be minimum 25.4 & 12.5 mm respectively. Type, grade, size, workmanship and finish of the material used shall be as per IS: 12933 (Part 2)/ 2003.

The header and riser assembly shall be designed for a working pressure of 2.5 kg/sq. cm and shall be tested for leakages at a minimum hydraulic pressure of 5 kg/sq. cm.

- (d) Sheet for absorber: Sheet for absorber shall be made of copper only. Type, grade, size, workmanship and finish of the material used shall be as per IS: 12933 (Part 2)/ 2003.
- **(e) Collector box insulation:** Insulation shall be provided at back and sides. Collector box insulation shall conform to IS: 12933 (Part 2)/ 2003.Glass wool& rock wool insulation, 50 mm thick for back & 25 mm thick for side can be accepted.
- **(f) Gaskets and Grommets:** Gaskets and grommets shall conform to IS: 12933 (Part 2)/ 2003
- **(g) Collector stand assembly:** Collector stand assembly shall be made of MS angle of minimum size 35x35x5 mm duly pre-treated and hot dip galvanized after fabrication. If during erection at site the zinc coating is punctured due to welding or any other reason, the punctured portion shall be painted (at least 2 coats) with silver paint. Alternatively tubular structure with powder coating could also be provided.

8.2.2 Insulated Hot Water Tank with jacket:

- (a) Water tank with heat exchanger: The hot water tank shall be non pressure type of capacity 200 Litres and made up of SS conforming to AISI 304/304 L with minimum 1.2 mm thick sheet & TIG welding. SS jacket around inner tank shall be there for circulation of primary heating medium (thermic fluid/ distilled water) from solar collector panel in close loop for heating secondary water stored in the tank. The outer shell shall be insulated preferably with thermal grade PUF of thickness 40 mm and clad with Aluminium/ GI sheet of minimum 24 SWG. PUF density shall be minimum 32 kg/ cu m. Alternatively minimum 50 mm thick Rock Wool slab with AL/ GI cladding can be used for insulation. A SS drain with SS cock shall be provided to take out sediments periodically.
- **(b) Primary liquid make-up:** The hot primary liquid recirculation system through the solar collector plate and jacket of hot water tank shall be by natural convection. A 5 litre capacity SS (utensil grade, 200 series) make up tank shall be given for make up of primary heating medium. This tank to be kept at top of the hot water tank.
- (c) Back-up Electrical heater: An electrical heater of 2 KW rating with built in thermostat shall be provided in the tank as 'back-up heater' for heating water in cloudy days. Location of heater shall be near the bottom of the tank. The heater shall be ISI marked and shall be fitted to the tank in such a manner so that total heat dissemination takes place in to water only. All electrical safety aspects shall be

addressed regarding fitment of the heater and proper earthing connection shall be provided for connecting the earthing wire with main earthing bus of the milk collection centre. The fitment of heater shall ensure easy maintenance/ replacement.

(d) Tank stand assembly: The tank stand assembly shall be made of MS angle of size 35x35x5 mm duly pre-treated and hot dip galvanized after fabrication. If during erection at site the zinc coating is punctured due to welding or any other reason, the punctured portion shall be painted (at least 2 coats) with silver paint. Alternatively tubular structure with powder coating could also be provided. This tank to be of height such that inlet of water tank is higher than solar collector.

8.2.3 Cold Water Storage Tank (This tank shall be included if the tank specified against clause number 8.1 is not included in the specification):

For storing cold water before feeding water to hot water storage tank of solar water heating system, a HDPE tank, two layer type of capacity 500 litre to be provided with a supporting stand. The tank to be provided with float valve, drain, & overflow and other standard accessories. The tank stand assembly shall be made of MS angle of size 35x35x5 mm duly pre-treated and hot dip galvanized after fabrication. If during erection at site the zinc coating is punctured due to welding or any other reason, the punctured portion shall be painted (at least 2 coats) with silver paint. Alternatively tubular structure with powder coating could also be provided.

The bottom level of this water tank shall be at a higher level than top of the hot water storage tank. Apart from pipeline to the hot water tank, a separate pipeline for cold water with a valve at the outlet up to the use point in the room with a tap shall be provided.

- **8.2.4 System interconnecting piping**: System interconnecting piping shall be of GI medium class (Class B), ISI marked. Piping is required between cold water tank out let to inlet of hot water tank and from hot water tank outlet to one point in BMC Tank area. Hot water piping to be duly insulated with 50 mm thick rock wool of 48 kg/ cu m density and 26 SWG aluminium cladding. Suitable piping connection of GI/SS to be provided between solar collector and hot water tank. All fittings, accessories, valves, vent, filter etc. required for smooth functioning of the system, shall be provided. Height of air vent pipe shall be more than the top of cold water supply tank.
- **8.2.5 Electrical Power Connection:** An isolator switch shall be provided near the solar heater unit duly protected from rain water to isolate the electrical connection during maintenance and also in case of any emergency situation.

9. Installation, Commissioning & Training 9.1 Installation

Unloading of BMC and accessories shall be arranged at site by purchaser at their cost, but advance intimation of dispatch of the consignment is to be given by the supplier to the purchaser/ client.

The installation work should be carried in the best workman like manner in conformity to the relevant codes of practices of BIS standards applicable for mechanical & electrical installation.

3 (three) ABC stored pressure type fire extinguisher of capacity 1 Kg. shall be supplied and installed by supplier.

Installation of all equipment & interconnecting piping, including minor civil works such as providing galvanized steel supports, SS base plates, clamps (hinged type) etc. required to secure the equipment & piping to walls and floors is included in the scope. Necessary cable trays, GI pipes/conduits, cable gland sockets at both ends, isolators, junction boxes etc are included in the scope of the contract to lay & connect all electrical and control cables. Cable trays and supporting steel members such as Galvanised angles/channel/flats, supply of CI covers for the pits etc shall be used and fixed/installed at appropriate places to ensure safe installation. The laying of cables on the floor or under the floor is not permitted.

The owner will undertake major civil works. The supplier shall make available all tools & tackles required to execute the job.

9.2 Commissioning:

Supplier shall arrange commissioning & performance trial runs of the bulk milk cooling system to the satisfaction of the client. The supplier shall supply all the consumables (excepting diesel for DG set) required during commissioning of the plant.

Along with the bulk milk cooler & DG Sets etc, the bidder shall quote for supply of spares along with prices for the complete system. A set of essential spares for the total installation as required by the user shall be worked out & finalized at the time of finalization of the contract. **The cost of spares should not be included in the main bid price.**

9.3 Tool Box

A GI sheet toolbox containing one set of all necessary tools required for regular maintenance of the unit shall be supplied along with the BMC.

9.4 Manual

Two sets of operation & maintenance manual, one in English & another in local language containing complete details of starting up, putting off, critical checks and day-to-day maintenance of the complete system shall be supplied. The manual should also have the required electrical circuit diagrams.

9.5 Training

Supplier shall arrange for training of the operating team for efficient operation and maintenance of the complete system.

10. AFTER SALES SERVICE, SERVICE CENTRE AND SERVICE CONTRACT

10.1 Obligation of BMC Package supplier for providing After Sales Service/ Warranty claims for BMC package components supplied.

It would be the responsibility of the contractor, for bought-out components of critical nature such as DG Set and Voltage stabilizer, to identify dealers/ agencies located in the region where BMC package would be installed. This is to facilitate fulfilling of the warranty obligations as per the contract and availing timely services by milk collection centre in cases of emergency.

To this effect BMC package supplier should select the suppliers for such components in the region in consultation with the client / NDDB SO. It is necessary to have this arrangement keeping need of the far off placed milk collection centres in view.

10.2 Service Centre

- a) Adequate & skilled manpower including a dedicated technician for maintenance & repairs of DG set. It shall be the responsibility of DG set supplier jointly with BMC supplier to provide necessary support to maintain smooth operation of the total package at Village.
- b) Telephone connections and communications to call the service team round the clock.
- c) Transport facilities: The centre is to have transport (owned or hired) available round the clock of adequate capacity to;

Provide rapid replacement of complete milk cooling unit or DG set, if necessary.

Ensure regular & continuous visits of the service team(s) to the collection centers.

- d) Maintenance workshop, including essential machine tools and hand tools to tackle any repair that may be required for the system and for regular dismantling and overhauling of diesel engines that would be necessary on a continuous basis.
- e) Stock of spare parts. (The list should be provided by the bidder.)

10.3 Service Contract (Optional)

The bidder is to quote for the service contract for a period of three years from the date of expiry of the warranty period. This is to include the cost of labour, materials, transport and incidentals, and be based on the unit rate per collection centre per year. This would involve the necessary teams and vehicles to provide continuous cover as follows:

Regular service visits to each collection centre every 8 weeks to clean and adjust all of the equipment (including topping up lube-oil levels etc.) as necessary.

To attend to emergency breakdowns, and to arrive at the milk collection centre within **three hours** of receiving intimation of breakdown.

In case of break down of BMC, provide emergency services for shifting of BMC milk to other locations as directed by clients. This arrangement shall be there as long as normal BMC operation is not restored.

11. Inspection

Client reserves right to inspect all the components of the bulk milk cooling system during fabrication/ manufacturing stage, finished stage before dispatch of the equipments. Before starting the fabrication work supplier shall submit QAP & QIP for approval from client. The milk cooling tank shall be checked with dye penetration test for welding defect, surface roughness check, water tightness test / hydraulic test.

12. General Requirement

12.1 Technical Details

The bidder shall provide all the technical details, as per the format enclosed as appendix over and above the general description in each section.

12.2 Makes of Items

The bidder shall refer Appendix for the list of makes of all the bought out items required to complete the package of the bulk milk cooling system. Bidder shall obtain necessary approval from client for all items included at the time of finalization of contract.

12.3 Drawing

Bidder shall submit a detailed general arrangement drawing for complete system giving complete details with bill of materials, size, capacity, quantity, material of construction, thickness etc.

12.4 Equipment Selection criteria

Bidder shall submit along with the offer detailed calculations with proper justification for selection of compressor (s), evaporator (s), condenser (s), fan (s), thickness of tank, milk pump, insulation material and thickness, DG Set etc.

13.0 Optional Items:

The bidder should also quote for the following optional items required to meet the specific need of the cluster milk collection centres.

13.1 Can Tipping Bar:

The general design of the can tipping bar should be a horizontal wooden bar supported on two legs. The legs would be grouted down to the floor with the help of grouting bolts.

Top Bar: It should be made of teak wood. The dimensions of the bar should be sufficient to take load of 40 L milk filled can and also the dynamic load due to jerk in manual handling of the filled cans.

Legs: The legs should be made of MS `C' class pipe. A provision to fix the structure on the foundation should be given - 2 nos.

Painting: All MS surfaces are to be painted with a coat of epoxy primer allowed by two coats of epoxy paint of ivory color after thorough de-rusting.

The height should match with the equipment layout/ balance tank of the milk collection centre.

<u>Important Note</u>: The cost of the Optional items shall not be included in calculation of the total bid price. In the event, the optional items are selected by the purchaser for package, the quoted price for the optional item shall include all incidental costs of installing that item as part of the contract.

APPENDIX

Format for technical details:

S.NO	DESCRIPTION	TECHNICAL DETAILS
A.	Bulk Milk Cooler tank	
1.	Capacity (rated and gross)	
2.	Make and model.	
3.	Material used for construction (SS 304/316)	
4.	Shape & Orientation:	
5.	Overall dimensions and weight.	
6.	Thickness of inner and outer SS shells	
7. 8.	Number of agitator(s) , RPM.	
9.	CIP facility: Manual or automatic with the details Type, thickness and efficiency of insulation.	
10.	Facility to measure milk volume (dip stick etc.)	
В.	Refrigeration unit	
1.	Make, model and size of compressor(s) at operating	
	conditions 0 ^U C evaporating & 60 ^U C Condensing	
	temperature.	
2. 3.	Make, model and size of condenser(s). Capacity of compressor(s) (Kcal/hr) at evaporating &	
٥.	condensing temperatures.	
4.	Capacity of condenser & no. of fans.	
5.	Receiver size & capacity	
6.	Thermostatic expansion valve, make, size, capacity	
7.	Overall dimensions and weight of the unit.	
8.	Type of refrigerant.	
C.	Design Parameters	
1.	Ambient temperature considered for design	
2.	Maximum cooling time considered for ALL & SECOND	
	milking.	
3.	Temperature range considered for ALL & SECOND	
	milking.	
D.	DG set	
	As per specifications and loading proposed at 7.1	
1.	Make and Model of the alternator.	
2.	KVA, Volts, Amps. & pF rating of the alternator	
3.	Model of the engine with no of cylinders.	
4.	BHP rating of the engine.	

S.NO	DESCRIPTION	TECHNICAL DETAILS
5.	Type of engine cooling- Air / Water – coolant cooled,	
6.	efficiency of the engine considered for selection Derating factors considered in the design/selection	
7.	Maximum current that set can withstand.	
/ .	Maximum current that set can wenstand.	
8.	Fuel Consumption On Genset at Load - lit/ Hr.	
	At – 25% Load	
	At- 50% Load At - 75% Load	
	At - 75% Load At -100%Load	
9.	Conformity to Noise & Emission Standards.	Attach certificate
10.	Controls & safeties for Engine & Alternator	Give details
11.	Voltage stabiliser and single-phase preventor	
E.	Electricals	
1.	Connected load in Watts & Amperes for :	
	Compressor(s)	
	Condenser fan(s)	
	Agitator(s).	
	Milk pump	
2.	Water heater. Maximum / surge current drawn by the compressor(s)	
۷.	(during starting).	
F.	Miscellaneous	
1.	Enclose the following:	
	a) Performance curves of the milk cooling tank i.e.	
	time (hrs) Vs temperature (Deg.C) curves.	
	b) The leaflet / catalogue of the alternator and engine	
	for the DG set. c) Performance chart of the DG set showing the fuel	
	consumption (litres/hr) at various loading conditions	
	and at maximum output (KW), variation of the	
	maximum output (KW) with respect to ambient	
	temperature assumed.	
2.	The following performance curves of the compressor(s):	
	 a) Evaporating temperature Vs Cooling capacity (kcal/hr) at various condensing temperatures. 	
	b) Compressor capacity (kcal/hr) Vs Power	
	consumption (Watts).	
3.	Specify the assumption(s), if any, made in design /	
	selection of any item including the tank, DG set etc.	description of the
		respective item)

Technical Data to be provided for solar hot water system offered as per format given below

Sno	Item	Unit	Details
Α	Solar flat plate collector		
	No of Cu risers	No.	
	Dia & thickness of Cu riser	mm	

	Dia & thickness of Cu header		
	Fin Material	+	
	Size of Collector	mm	
	Toughened glass thickness	mm	
	Thickness of Al side for frame	mm	
	Thickness of Al bottom sheet	mm	
	Thickness of support for glass retaining	mm	
	Thickness for entire body	mm	
	Finish of frame	111111	
	Insulation material/thickness	mm	
-	Hardware	SS/MS	
-	Testing Pressure	Bar	
	Solar Absorptivity	Dai	
В	Hot Water tank	+ +	
<u> </u>	Tank type-Direct/indirect	+ +	
-	Capacity	Litre	
-	Tank Material-SS 304/SS304 L	Litte	
	Tank reaction 33 304/33304 E	mm	
	Tank dome plate thickness	mm	
	Tank welding type-TIG/Plasma TIG	1111111	
		+ +	
-	Heat exchanger area	Sq M	
-	Treat exchanger area	39 11	
		+	
-	Insulation material/thickness	mm	
	Cladding material/thickness	mm	
-	Make up tank capacity	Litre	
-	Material of make up tank	Litte	
С	Stand for Hot water /cold water tank	† †	
	Stand Material with finish type	† †	
	Angle/pipe detail	mm	
D	Electrical back up Heater	1	
	Heater rating/nos	KW	
	Thermostat	Yes/no	
Е	Cold water tank	1.00,110	
	Material	† †	
	Capacity	Litre	
F	G I B class piping for cold/hot water		
-	Dia of piping	mm	
	I S IC OI PIPILIS		

Schedule of items

	Schedule of Items for Bulk Milk Cooler (To be in conformity with Specifications & scope of supply)	
Sr.		
No.	Item Description	Quantity
Α	Bulk Cooling Tank with Refrigeration Control Panel	
	Bulk Milk Cooler tank complete with cover, Refrigeration unit and	
	standard accessories.	
	Tank and pipe cleaning brushes	
	Operation and Maintenance Manual	

	Tool Box	
	Spares	
В	Electricals	
	Electrical and control Panels, Servo Voltage stabilizer,	
	Power & Control	
	cabling, Earthing, C I Covers etc	
	DG Set with alternator and engine, acoustic	
	enclosure, main & control	
	panels	
	Exhaust piping , Day tank , GI trays	
	One barrel for Diesel and hand pump	
	Battery with battery box ,	
С	Miscellaneous Items	
	SS Pipe and Fittings, Inlet Funnel with SS Strainer &	
	Milk Reception	
	Tray/ balance tank (applicable for gravity feed	
	system)	
	Interconnecting SS Pipes and Fittings, Food Grade	
	Tanker Loading	
	Hose Size 38mm complete with end connections	
D	SS Pipe and Fittings & Tank (Pumped feed system)	
	Tanker Loading Pump Cap. 5000 LPH at 10 MWC	
	SS Centrifugal Monobloc sanitary Design pump with single	
	mechanical seal as per	
	Specifications.	
E	HDPE Tank of cap. 1000 Liters as per IS standards	
	Solar water heater 200 LPD/ Any other heater as per	
F	specs	
G	SS Hot Water Piping	
Н	Structural materials etc for tank mounting	

Note:

- (1) The contractor is responsible for supply and execution of all the equipment/material, instruments, controls, safeties included in the BMC packages. It would be the responsibility of the supplier to ensure that any item not appearing in the above specs but felt essential for safe & efficient operation of any component of the system is included without extra cost in the contract to make the BMC package complete.
- (2) The bidders can also offer alternate equipment/ system for better efficiency and improved performance. A detailed offer to this effect with full technical details shall be given in the bid. However, the user reserves the right to reject or adopt the alternative equipment.

APPENDIX

	LIST OF APPROVED MAKES OF BOUGHT OUT ITEMS					
S.N.	S.N. ITEM DESCRIPTION APPROVED MAKES					
1.0	SS PUMPS	APV/ ALFA LAVAL (LKM)/ TETRA PACK/ L&T/ IDMC				
2.0	SS VALVES & FITTINGS	IDMC/ALFA LAVAL (LKM)				
3.0	REFRIGERATION CONTROLS	DANFOSS/ALCO/SANSEN/PARKER/AMERICAN				
		SPECIALITIES				

4.0	SS PIPES	BHANDARI FOILS/RATNAMANI/ APEX TUBES
		HEAVY METALS
5.0	SS PNEUMATIC VALVES	GEA /ALFA LAVAL (LKM)/KEYSTONE/ IDMC
6.0	MOTORS	SIEMENS/ABB /KIRLOSKAR/ BHARATH BIJLEE/SHARP/LUBI
	CABLES - ARMOURED	FINOLEX/UNIVERSAL/CCI/NICCO/FORT GLOSTER/R R CABLE/HI-LIGHT/GREEN ELE/POLY CAB
	Starters	L & T.
	Contactor	Telemechaniq/Siemens/L & T/sprecher+schuh
10.0	PUSH BUTTONS	L&T/SIEMENS/ABB / SCHNEIDER
	Relays	SEGC/Siemens
12.0	INDICATING LAMPS	L&T/SIEMENS/SCHNEIDER/ TECHNIC /VAISHANAV / PRECITECH
13.0	Current Transformers	Карра
14.0	PRESSURE SWITCH	DANFOSS/ALCO / PARKER/HANSEN
15.0	DIGITAL INDICATOR	HONEYWELL/RAXIX/MASIBUS/PROTOCOL/VIBHUTI
16.0	D G SET	CUMMINS/KIRLOSKAR/MAHINDRA/EICHER/GREAVE S/ASHOK LEYLAND
17.0	Alternator	Stamford / Leroysomler
18.0	BATTERY FOR THE DG SET	EXIDE/STANDARD-FURUKOWA/ PRESTOLITE/AMCO -YUVASA/AMARON
19.0	STABILISER	SUVIK/MICROTECH/SEN&PANDIT/PACE/POWER ENGINEERS/ ASABA/GURU NANAK
20.0	SOLAR HOT WATER SYSTEM	TATA BP SOLAR/JAIN IRIGATION/ RACOLD SALORE/SUDARSHAN SAUR/STEEL HACKS/ DGS&D- GOI APPROVED SUPPLIERS.
21.0	Hot Water Electric Geyser	SPEARHOT/RACOLD/ USHA/BATLIBOI/BAJAJ
22.0	HDPE TANK-HEAVY DUTY	SINTEX/ KAVERI/ HITANK

5. Inspections and Tests

The following inspections and tests shall be performed:

Inspection and Tests

The Purchaser or its representative shall have the right to inspect and/or test the Goods to confirm their conformity to the Contract. The inspections and tests may be conducted on the premises of the Supplier or its subcontractor(s), at point of delivery and/or at the Good's final destination.

Should any inspected or tested Goods fail to conform to the Specifications, the Purchaser may reject them and the Supplier shall either replace the rejected Goods or make all alternations necessary to meet specification requirements free of cost to the Purchaser.

The Purchaser's right to inspect, test, and, where necessary, reject the Goods after the Goods arrival at the destination shall in no way be limited or waived by reason of the Goods having previously been inspected, tested and passed by the Purchaser or its representative prior to Goods shipment.

6. PROFORMA OF CERTIFICATE FOR ISSUE BY THE PURCHASER AFTER SUCCESSFUL INSTALLATION AND STARTUP OF THE SUPPLIED GOODS

[This	is to be	attached for supply, erection, supervision of erection and startup contracts only	,]
No.		Date:	
M/s.			
Sub:	<u>Certifi</u>	icate of startup of the supplied Goods	
1.	condit No. 2)	s to certify that the plant/s as detailed below has/have been received in good tion along with all the standard and special accessories (subject to remarks in Pa) and a set of spares in accordance with the Contract/Specifications. The same hastalled and commissioned. Contract No	
	(b)	Description of the plant	
	(c)	Plant Nos	
	(d)	Quantity	
	(e)	Rail/Roadways Receipt Nodated	
	(f)	Name of the consignee	_
	(g)	Date of start up and proving test	
2.	Detail	s of accessories/spares not yet supplied and recoveries to be made on that account	nt.
	<u>S. No.</u>	<u>Description</u> <u>Amount to be recovered</u>	
3.	-	roving test has been done to our entire satisfaction and operators have been trainerate the plant.	ıed
4.	The su	upplier has fulfilled his contractual obligations satisfactorily. *	
		or	

The supplier has failed to fulfill his contractual obligations with regard to the following:

	(b)
	(c)
	(d)
5.	The amount of recovery on account of non-supply of accessories and spares is given under Para No. 2.
6.	The amount of recovery on account of failure of the supplier to meet his contractual obligations is as indicated in endorsement of the letter.
	Signature
	Name

* Explanatory notes for filling up the certificates:

(a)

(a) He has adhered to the time schedule specified in the contract in dispatching the documents/drawings pursuant to Technical Specifications.

Designation with Stamp

- (b) He has supervised the startup of the plan in time i.e., within the period specified in the contract from the date of intimation by the Purchaser in respect of the installation of the plant.
- (c) Training of personnel has been done by the supplier as specified in the contract
- (d) In the event of documents/drawings having not been supplied or installation and startup of the plant have been delayed on account of the supplier, the extent of delay should always be mentioned.

7. PERFORMA FOR PERFORMANCE STATEMENT

[Please see ITB Clause 38.2 and Section III-Evaluation and Qualification Criteria]

Bid No	Date of opening		Performance Statem	ent (for a period of last Time	•		
		Name o	of the Firm				
Order placed by (full address of Purchaser)	Order No. and date	Description and quantity of ordered equipment	Value of order	<u>Date of completi</u>	on of delivery	Remarks indicating reasons for late delivery, if any	Has the equipment been satisfactorily functioning? (Attach a certificate form the Purchaser/Consignee)
1	2	3	4	As per contract 5	Actual 6	7	8
Signature and seal o	f the Bidder						

PART 3 – CONTRACT

Section VII. General Conditions of Contract

Table of Clauses

1.	DEFINITIONS	
2.	CONTRACT DOCUMENTS	82
3.	FRAUD AND CORRUPTION	82
4.	INTERPRETATION	83
5.	LANGUAGE	84
6.	DELETED	84
7.	ELIGIBILITY	84
8.	NOTICES	85
9.	GOVERNING LAW	85
10.	SETTLEMENT OF DISPUTES	85
11.	INSPECTIONS AND AUDIT BY THE BANK	85
12.	SCOPE OF SUPPLY	
13.	DELIVERY AND DOCUMENTS	86
14.	SUPPLIER'S RESPONSIBILITIES	86
15.	CONTRACT PRICE	86
16.	TERMS OF PAYMENT	86
17.	TAXES AND DUTIES	
18.	PERFORMANCE SECURITY	87
19.	COPYRIGHT	
20.	CONFIDENTIAL INFORMATION	87
21.	SUBCONTRACTING	88
22.	SPECIFICATIONS AND STANDARDS	
23.	PACKING AND DOCUMENTS	
24.	INSURANCE	89
25.	TRANSPORTATION	89
26.	INSPECTIONS AND TESTS	89
27.	LIQUIDATED DAMAGES	90
28.	WARRANTY	91
29.	PATENT INDEMNITY	91
30.	LIMITATION OF LIABILITY	
31.	CHANGE IN LAWS AND REGULATIONS	93
32.	FORCE MAJEURE	
33.	CHANGE ORDERS AND CONTRACT AMENDMENTS	
34.	EXTENSIONS OF TIME	
35.	TERMINATION	
36.	ASSIGNMENT	96

Section VII. General Conditions of Contract

1. Definitions

The following words and expressions shall have the meanings hereby assigned to them:

- (a) "Bank" means the World Bank and refers to the International Bank for Reconstruction and Development (IBRD) or the International Development Association (IDA).
- (b) "Contract" means the Contract Agreement entered into between the Purchaser and the Supplier, together with the Contract Documents referred to therein, including all attachments, appendices, and all documents incorporated by reference therein.
- (c) "Contract Documents" means the documents listed in the Contract Agreement, including any amendments thereto.
- (d) "Contract Price" means the price payable to the Supplier as specified in the Contract Agreement, subject to such additions and adjustments thereto or deductions there from, as may be made pursuant to the Contract.
- (e) "Day" means calendar day.
- (f) "Completion" means the fulfillment of the Related Services by the Supplier in accordance with the terms and conditions set forth in the Contract.
- (g) "GCC" means the General Conditions of Contract.
- (h) "Goods" means all of the commodities, raw material, machinery and equipment, and/or other materials that the Supplier is required to supply to the Purchaser under the Contract.
- (i) "Purchaser's Country" is India.
- (j) "Purchaser" means the entity purchasing the Goods and Related Services, as specified in the SCC.
- (k) "Related Services" means the services incidental to the supply of the goods, such as insurance, installation, start-up, training and initial maintenance and other such obligations of the Supplier under the Contract.
- (l) "SCC" means the Special Conditions of Contract.
- (m) "Subcontractor" means any natural person, private or

government entity, or a combination of the above, to whom any part of the Goods to be supplied or execution of any part of the Related Services is subcontracted by the Supplier.

- (n) "Supplier" means the natural person, private or government entity, or a combination of the above, whose bid to perform the Contract has been accepted by the Purchaser and is named as such in the Contract Agreement.
- (o) "The Project Site," where applicable, means the place named in the **SCC**.

2. Contract Documents

2.1 Subject to the order of precedence set forth in the Contract Agreement, all documents forming the Contract (and all parts thereof) are intended to be correlative, complementary, and mutually explanatory. The Contract Agreement shall be read as a whole.

3. Fraud and Corruption

- 3.1 If the Purchaser determines that the Supplier or its agents (whether declared or not), sub-contractors, sub-consultants, service providers, and any personnel thereof has engaged in corrupt, fraudulent, collusive, coercive or obstructive practices, in competing for or in executing the Contract, then the Purchaser may, after giving 14 days notice to the Supplier, terminate the Supplier's employment under the Contract and cancel the contract, and the provisions of Clause 35 shall apply as if such termination had been made under Sub-Clause 35.1.
 - (a) For the purposes of this Sub-Clause:
 - (i) "corrupt practice" is the offering, giving, receiving or soliciting, directly or indirectly, of anything of value to influence improperly the actions of another party;
 - (ii) "fraudulent practice" is any act or omission, including a misrepresentation, that knowingly or recklessly misleads, or attempts to mislead, a party to obtain a financial or other benefit or to avoid an obligation;
 - (iii) "collusive practice" is an arrangement between two or more parties designed to achieve an improper purpose, including to influence improperly the actions of another party;
 - (iv) "coercive practice" is impairing or harming, or threatening to impair or harm, directly or indirectly, any party or the property of the party to influence improperly the actions of a party;

- (v) "obstructive practice" is
- (aa) deliberately destroying, falsifying, altering or concealing of evidence material to the investigation or making false statements to investigators in order to materially impede a Bank investigation into allegations of a corrupt, fraudulent, coercive or collusive practice; and/or threatening, harassing or intimidating any party to prevent it from disclosing its knowledge of matters relevant to the investigation or from pursuing the investigation, or
- (bb) acts intended to materially impede the exercise of the Bank's inspection and audit rights provided for under Clause 11 [Inspections and Audits by the Bank].
- 3.2 Should the Supplier or its agents (whether declared or not), sub-contractors, sub-consultants, service providers, and any personnel thereof be determined to have engaged in corrupt, fraudulent, collusive, coercive, or obstructive practice, the Bank will sanction a firm or individual, at any time, in accordance with prevailing Bank's sanctions procedures, including by publicly declaring such firm or individual ineligible, either indefinitely or for a stated period of time: (i) to be awarded a Bank-financed contract; and (ii) to be a nominated sub-contractor, consultant, supplier or services provider of an otherwise eligible firm being awarded a Bank-financed contract.

4. Interpretation

- 4.1 If the context so requires it, singular means plural and vice versa.
- 4.2 Inco terms
- (a) Unless inconsistent with any provision of the Contract, the meaning of any trade term and the rights and obligations of parties there under shall be as prescribed by Inco terms.
- (b) The terms EXW and other similar terms, when used, shall be governed by the rules prescribed in the current edition of Inco terms specified in the **BDS** and published by the International Chamber of Commerce in Paris, France.

4.2 Entire Agreement

The Contract constitutes the entire agreement between the Purchaser and the Supplier and supersedes all communications, negotiations and agreements (whether written or oral) of the parties with respect thereto made prior to the date of Contract.

4.3 Amendment

No amendment or other variation of the Contract shall be valid unless it is in writing, is dated, expressly refers to the Contract, and is signed by a duly authorized representative of each party thereto.

4.4 Nonwaiver

- (a) Subject to GCC Sub-Clause 4.5(b) below, no relaxation, forbearance, delay, or indulgence by either party in enforcing any of the terms and conditions of the Contract or the granting of time by either party to the other shall prejudice, affect, or restrict the rights of that party under the Contract, neither shall any waiver by either party of any breach of Contract operate as waiver of any subsequent or continuing breach of Contract.
- (b) Any waiver of a party's rights, powers, or remedies under the Contract must be in writing, dated, and signed by an authorized representative of the party granting such waiver, and must specify the right and the extent to which it is being waived.

4.5 Severability

If any provision or condition of the Contract is prohibited or rendered invalid or unenforceable, such prohibition, invalidity or unenforceability shall not affect the validity or enforceability of any other provisions and conditions of the Contract.

5. Language

- 5.1 The Contract as well as all correspondence and documents relating to the Contract exchanged by the Supplier and the Purchaser, shall be English. Supporting documents and printed literature that are part of the Contract may be in another language provided they are accompanied by an accurate translation of the relevant passages in English language, in which case, for purposes of interpretation of the Contract, this translation shall govern.
- 5.2 The Supplier shall bear all costs of translation to the governing language and all risks of the accuracy of such translation, for documents provided by the Supplier.

6. Deleted

7. Eligibility

- 7.1 The Supplier and its Subcontractors shall have the nationality of an eligible country. A Supplier or Subcontractor shall be deemed to have the nationality of a country if it is a citizen or constituted, incorporated, or registered, and operates in conformity with the provisions of the laws of that country.
- 7.2 All Goods and Related Services to be supplied under the

Contract and financed by the Bank shall have their origin in Eligible Countries. For the purpose of this Clause, origin means the country where the goods have been grown, mined, cultivated, produced, manufactured, or processed; or through manufacture, processing, or assembly, another commercially recognized article results that differs substantially in its basic characteristics from its components.

8. Notices

- 8.1 Any notice given by one party to the other pursuant to the Contract shall be in writing to the address specified in the SCC. The term "in writing" means communicated in written form with proof of receipt.
- 8.2 A notice shall be effective when delivered or on the notice's effective date, whichever is later.

9. Governing Law

9.1 The Contract shall be governed by and interpreted in accordance with the laws of the Union of India.

10. Settlement of Disputes

- 10.1 The Purchaser and the Supplier shall make every effort to resolve amicably by direct informal negotiation any disagreement or dispute arising between them under or in connection with the Contract.
- 10.2 If, after twenty-eight (28) days, the parties have failed to resolve their dispute or difference by such mutual consultation, then either the Purchaser or the Supplier may give notice to the other party of its intention to commence arbitration, as hereinafter provided, as to the matter in dispute, and no arbitration in respect of this matter may be commenced unless such notice is given. Any dispute or difference in respect of which a notice of intention to commence arbitration has been given in accordance with this Clause shall be finally settled by arbitration. Arbitration may be commenced prior to or after delivery of the Goods under the Contract. Arbitration proceedings shall be conducted in accordance with the rules of procedure specified in the SCC.
- 10.3 Notwithstanding any reference to arbitration herein,
 - (a) the parties shall continue to perform their respective obligations under the Contract unless they otherwise agree; and
 - (b) the Purchaser shall pay the Supplier any monies due the Supplier.

11. Inspections and Audit by the Bank

11.1 The Supplier shall permit the Bank and/or persons appointed by the Bank to inspect the Supplier's offices and/or the accounts and records of the Supplier and its sub-contractors relating to the performance of the Contract, and to have such accounts and records audited by auditors appointed by the Bank if required by the Bank. The Supplier's attention is drawn to Clause 3, which provides, inter alia, that acts intended to materially impede the exercise of the Bank's inspection and audit rights provided for under Sub-Clause 11.1 constitute a prohibited practice subject to contract termination (as well as to a determination of ineligibility under the Procurement Guidelines).

12. Scope of Supply

12.1 The Goods and Related Services to be supplied shall be as specified in the Special Condition of Contract.

13. Delivery and Documents

13.1 Subject to GCC Sub-Clause 33.1, the Delivery of the Goods and Completion of the Related Services shall be in accordance with the Delivery and Completion Schedule specified in the Schedule of Requirements. The details of shipping and other documents to be furnished by the Supplier are specified in the SCC.

14. Supplier's Responsibilities

14.1 The Supplier shall supply all the Goods and Related Services included in the Scope of Supply in accordance with GCC Clause 12, and the Delivery and Completion Schedule, as per GCC Clause 13.

15. Contract Price

15.1 Prices charged by the Supplier for the Goods supplied and the Related Services performed under the Contract shall not vary from the prices quoted by the Supplier in its bid, with the exception of any price adjustments authorized in the SCC.

16. Terms of Payment

- 16.1 The Contract Price, including any Advance Payments, if applicable, shall be paid as specified in the **SCC**.
- 16.2 The Supplier's request for payment shall be made to the Purchaser in writing, accompanied by invoices describing, as appropriate, the Goods delivered and Related Services performed, and by the documents submitted pursuant to GCC Clause 13 and upon fulfillment of all other obligations stipulated in the Contract.
- 16.3 Payments shall be made promptly by the Purchaser, but in no case later than sixty (60) days after submission of an invoice or request for payment by the Supplier, and after the Purchaser has accepted it.
- 16.4 The payments shall be made in Indian Rupees to the Supplier under this Contract.
- 16.5 In the event that the Purchaser fails to pay the Supplier any payment by its due date or within the period set forth in the SCC, the Purchaser shall pay to the Supplier interest on the amount of such delayed payment at the rate shown in the SCC, for the period of delay until payment has been made in full, whether before or after judgment or arbitrage award.

16.6 Invoices to be raised in the name of our Union.

16.7 All taxes should be charged in Invoice.

16.8 "C Form" will be issued by Union.

17. Taxes and Duties

The Supplier shall be entirely responsible for all taxes, duties, license fees, etc., incurred until delivery of the contracted Goods to the Purchaser.

18. Performance Security

- 18.1 If required as specified in the SCC, the Supplier shall, within twenty-eight (21) days of the notification of contract award, provide a performance security for the performance of the Contract in the amount specified in the SCC.
- 18.2 The proceeds of the Performance Security shall be payable to the Purchaser as compensation for any loss resulting from the Supplier's failure to complete its obligations under the Contract.
- 18.3 As specified in the SCC, the Performance Security shall be denominated in the Indian Rupees, and shall be in one of the format stipulated by the Purchaser in the SCC, or in another format acceptable to the Purchaser.
- 18.4 The Performance Security shall be discharged by the Purchaser and returned to the Supplier not later than twenty-eight (28) days following the date of Completion of the Supplier's performance obligations under the Contract, including any warranty obligations, unless specified otherwise in the SCC.

19. Copyright

19.1 The copyright in all drawings, documents, and other materials containing data and information furnished to the Purchaser by the Supplier herein shall remain vested in the Supplier, or, if they are furnished to the Purchaser directly or through the Supplier by any third party, including suppliers of materials, the copyright in such materials shall remain vested in such third party

20. Confidential Information

20.1 The Purchaser and the Supplier shall keep confidential and shall not, without the written consent of the other party hereto, divulge to any third party any documents, data, or other information furnished directly or indirectly by the other party hereto in connection with the Contract, whether such information has been furnished prior to, during or following completion or termination of the Contract. Notwithstanding the above, the Supplier may furnish to its Subcontractor such documents, data, and other information it receives from the Purchaser to the extent required for the Subcontractor to perform its work under the Contract, in which event the Supplier shall obtain from such Subcontractor an undertaking

- of confidentiality similar to that imposed on the Supplier under GCC Clause 20.
- 20.2 The Purchaser shall not use such documents, data, and other information received from the Supplier for any purposes unrelated to the contract. Similarly, the Supplier shall not use such documents, data, and other information received from the Purchaser for any purpose other than the performance of the Contract.
- 20.3 The obligation of a party under GCC Sub-Clauses 20.1 and 20.2 above, however, shall not apply to information that:
- (a) the Purchaser or Supplier need to share with the Bank or other institutions participating in the financing of the Contract;
- (b) now or hereafter enters the public domain through no fault of that party;
- (c) can be proven to have been possessed by that party at the time of disclosure and which was not previously obtained, directly or indirectly, from the other party; or
- (d) otherwise lawfully becomes available to that party from a third party that has no obligation of confidentiality.
- 20.4 The above provisions of GCC Clause 20 shall not in any way modify any undertaking of confidentiality given by either of the parties hereto prior to the date of the Contract in respect of the Supply or any part thereof.
- 20.5 The provisions of GCC Clause 20 shall survive completion or termination, for whatever reason, of the Contract.

21. Subcontracting

- 21.1 The Supplier shall notify the Purchaser in writing of all subcontracts awarded under the Contract if not already specified in the bid. Such notification, in the original bid or later shall not relieve the Supplier from any of its obligations, duties, responsibilities, or liability under the Contract.
- 21.2 Subcontracts shall comply with the provisions of GCC Clauses 3 and 7.

22. Specifications and Standards

- 22.1 Technical Specifications and Drawings
- (a) The Goods and Related Services supplied under this Contract shall conform to the technical specifications and standards mentioned in Section VI, Schedule of Requirements and, when no applicable standard is mentioned, the standard shall be equivalent or superior to the official standards whose application is appropriate to the Goods' country of origin.

- (b) The Supplier shall be entitled to disclaim responsibility for any design, data, drawing, specification or other document, or any modification thereof provided or designed by or on behalf of the Purchaser, by giving a notice of such disclaimer to the Purchaser.
- (c) Wherever references are made in the Contract to codes and standards in accordance with which it shall be executed, the edition or the revised version of such codes and standards shall be those specified in the Schedule of Requirements. During Contract execution, any changes in any such codes and standards shall be applied only after approval by the Purchaser and shall be treated in accordance with GCC Clause 33.

23. Packing and Documents

- 23.1 The Supplier shall provide such packing of the Goods as is required to prevent their damage or deterioration during transit to their final destination, as indicated in the Contract. During transit, the packing shall be sufficient to withstand, without limitation, rough handling and exposure to extreme temperatures, salt and precipitation, and open storage. Packing case size and weights shall take into consideration, where appropriate, the remoteness of the goods' final destination and the absence of heavy handling facilities at all points in transit.
- 23.2 The packing, marking, and documentation within and outside the packages shall comply strictly with such special requirements as shall be expressly provided for in the Contract, including additional requirements, if any, specified in the **SCC**, and in any other instructions ordered by the Purchaser.

24. Insurance

24.1 Unless otherwise specified in the SCC, the Goods supplied under the Contract shall be fully insured—against loss or damage incidental to manufacture or acquisition, transportation, storage, and delivery, in accordance with the applicable Inco terms or in the manner specified in the SCC.

25. Transportation

25.1 Unless otherwise specified in the **SCC**, responsibility for arranging transportation of the Goods shall be in accordance with the specified Inco terms.

26. Inspections and Tests

- 26.1 The Supplier shall at its own expense and at no cost to the Purchaser carry out all such tests and/or inspections of the Goods and Related Services as are specified in the SCC.
- 26.2 The inspections and tests may be conducted on the premises of the Supplier or its Subcontractor, at point of delivery, and/or at the Goods' final destination, or in another place in the Purchaser's Country as specified in the SCC. Subject to GCC Sub-Clause 26.3, if conducted on the premises of the Supplier or its Subcontractor, all reasonable facilities and assistance,

- including access to drawings and production data, shall be furnished to the inspectors at no charge to the Purchaser.
- 26.3 The Purchaser or its designated representative shall be entitled to attend the tests and/or inspections referred to in GCC Sub-Clause 26.2, provided that the Purchaser bear all of its own costs and expenses incurred in connection with such attendance including, but not limited to, all traveling and board and lodging expenses.
- 26.4 Whenever the Supplier is ready to carry out any such test and inspection, it shall give a reasonable advance notice, including the place and time, to the Purchaser. The Supplier shall obtain from any relevant third party or manufacturer any necessary permission or consent to enable the Purchaser or its designated representative to attend the test and/or inspection.
- 26.5 The Purchaser may require the Supplier to carry out any test and/or inspection not required by the Contract but deemed necessary to verify that the characteristics and performance of the Goods comply with the technical specifications codes and standards under the Contract, provided that the Supplier's reasonable costs and expenses incurred in the carrying out of such test and/or inspection shall be added to the Contract Price. Further, if such test and/or inspection impedes the progress of manufacturing and/or the Supplier's performance of its other obligations under the Contract, due allowance will be made in respect of the Delivery Dates and Completion Dates and the other obligations so affected.
- 26.6 The Supplier shall provide the Purchaser with a report of the results of any such test and/or inspection.
- 26.7 The Purchaser may reject any Goods or any part thereof that fail to pass any test and/or inspection or do not conform to the specifications. The Supplier shall either rectify or replace such rejected Goods or parts thereof or make alterations necessary to meet the specifications at no cost to the Purchaser, and shall repeat the test and/or inspection, at no cost to the Purchaser, upon giving a notice pursuant to GCC Sub-Clause 26.4.
- 26.8 The Supplier agrees that neither the execution of a test and/or inspection of the Goods or any part thereof, nor the attendance by the Purchaser or its representative, nor the issue of any report pursuant to GCC Sub-Clause 26.6, shall release the Supplier from any warranties or other obligations under the Contract.

27. Liquidated Damages

27.1 Except as provided under GCC Clause 32, if the Supplier fails to deliver any or all of the Goods by the Date(s) of delivery or perform the Related Services within the period specified in the Contract, the Purchaser may without prejudice to all its other

remedies under the Contract, deduct from the Contract Price, as liquidated damages, a sum equivalent to the percentage specified in the **SCC** of the delivered price of the delayed Goods or unperformed Services for each week or part thereof of delay until actual delivery or performance, up to a maximum deduction of the percentage specified in those **SCC**. Once the maximum is reached, the Purchaser may terminate the Contract pursuant to GCC Clause 35.

28. Warranty

- 28.1 The Supplier warrants that all the Goods are new, unused, and of the most recent or current models, and that they incorporate all recent improvements in design and materials, unless provided otherwise in the Contract.
- 28.2 Subject to GCC Sub-Clause 22.1(b), the Supplier further warrants that the Goods shall be free from defects arising from any act or omission of the Supplier or arising from design, materials, and workmanship, under normal use in the conditions prevailing in the country of final destination.

28.3 **For BMCU:**

The warranty should be 24 months from the date of supply & 18 months from the date of commissioning whichever is earlier.

For Solar Water Heating System Min.5Years

For DG set:

DG set shall be used as a stand by therefore warranty should be five years or 2000 hours (whichever is earlier). Supplier shall be supplied filters/spares along with DG set for trouble shout operation up to five years.

- 28.4 The Purchaser shall give notice to the Supplier stating the nature of any such defects together with all available evidence thereof, promptly following the discovery thereof. The Purchaser shall afford all reasonable opportunity for the Supplier to inspect such defects.
- 28.5 Upon receipt of such notice, the Supplier shall, within the period specified in the SCC, expeditiously repair or replace the defective Goods or parts thereof, at no cost to the Purchaser.
- 28.6 If having been notified, the Supplier fails to remedy the defect within the period specified in the SCC, the Purchaser may proceed to take within a reasonable period such remedial action as may be necessary, at the Supplier's risk and expense and without prejudice to any other rights which the Purchaser may have against the Supplier under the Contract.

29. Patent

29.1 The Supplier shall, subject to the Purchaser's compliance with

Indemnity

GCC Sub-Clause 29.2, indemnify and hold harmless the Purchaser and its employees and officers from and against any and all suits, actions or administrative proceedings, claims, demands, losses, damages, costs, and expenses of any nature, including attorney's fees and expenses, which the Purchaser may suffer as a result of any infringement or alleged infringement of any patent, utility model, registered design, trademark, copyright, or other intellectual property right registered or otherwise existing at the date of the Contract by reason of:

- (a) the installation of the Goods by the Supplier or the use of the Goods in the country where the Site is located; and
- (b) the sale in any country of the products produced by the Goods.

Such indemnity shall not cover any use of the Goods or any part thereof other than for the purpose indicated by or to be reasonably inferred from the Contract, neither any infringement resulting from the use of the Goods or any part thereof, or any products produced thereby in association or combination with any other equipment, plant, or materials not supplied by the Supplier, pursuant to the Contract.

- 29.2 If any proceedings are brought or any claim is made against the Purchaser arising out of the matters referred to in GCC Sub-Clause 29.1, the Purchaser shall promptly give the Supplier a notice thereof, and the Supplier may at its own expense and in the Purchaser's name conduct such proceedings or claim and any negotiations for the settlement of any such proceedings or claim.
- 29.3 If the Supplier fails to notify the Purchaser within twenty-eight (28) days after receipt of such notice that it intends to conduct any such proceedings or claim, then the Purchaser shall be free to conduct the same on its own behalf.
- 29.4 The Purchaser shall, at the Supplier's request, afford all available assistance to the Supplier in conducting such proceedings or claim, and shall be reimbursed by the Supplier for all reasonable expenses incurred in so doing.
- 29.5 The Purchaser shall indemnify and hold harmless the Supplier and its employees, officers, and Subcontractors from and against any and all suits, actions or administrative proceedings, claims, demands, losses, damages, costs, and expenses of any nature, including attorney's fees and expenses, which the Supplier may suffer as a result of any infringement or alleged infringement of any patent, utility model, registered design,

trademark, copyright, or other intellectual property right registered or otherwise existing at the date of the Contract arising out of or in connection with any design, data, drawing, specification, or other documents or materials provided or designed by or on behalf of the Purchaser.

30. Limitation of Liability

- 30.1 Except in cases of criminal negligence or willful misconduct,
 - (a) the Supplier shall not be liable to the Purchaser, whether in contract, tort, or otherwise, for any indirect or consequential loss or damage, loss of use, loss of production, or loss of profits or interest costs, provided that this exclusion shall not apply to any obligation of the Supplier to pay liquidated damages to the Purchaser and
 - (b) the aggregate liability of the Supplier to the Purchaser, whether under the Contract, in tort or otherwise, shall not exceed the total Contract Price, provided that this limitation shall not apply to the cost of repairing or replacing defective equipment, or to any obligation of the supplier to indemnify the purchaser with respect to patent infringement

31. Change in Laws and Regulations

Unless otherwise specified in the Contract, if after the date of 28 days prior to date of Bid submission, any law, regulation, ordinance, order or bylaw having the force of law is enacted, promulgated, abrogated, or changed in India, where the Site is located (which shall be deemed to include any change in interpretation or application by the competent authorities) that subsequently affects the Delivery Date and/or the Contract Price, then such Delivery Date and/or Contract Price shall be correspondingly increased or decreased, to the extent that the Supplier has thereby been affected in the performance of any of its obligations under the Contract. Notwithstanding the foregoing, such additional or reduced cost shall not be separately paid or credited if the same has already been accounted for in the price adjustment provisions where applicable, in accordance with GCC Clause

32. Force Majeure

- 32.1 The Supplier shall not be liable for forfeiture of its Performance Security, liquidated damages, or termination for default if and to the extent that its delay in performance or other failure to perform its obligations under the Contract is the result of an event of Force Majeure.
- 32.2 For purposes of this Clause, "Force Majeure" means an event or situation beyond the control of the Supplier that is not foreseeable, is unavoidable, and its origin is not due to negligence or lack of care on the part of the Supplier. Such events may include, but not be limited to, acts of the Purchaser in its sovereign capacity, wars or revolutions, fires, floods,

epidemics, quarantine restrictions, and freight embargoes.

32.3 If a Force Majeure situation arises, the Supplier shall promptly notify the Purchaser in writing of such condition and the cause thereof. Unless otherwise directed by the Purchaser in writing, the Supplier shall continue to perform its obligations under the Contract as far as is reasonably practical, and shall seek all reasonable alternative means for performance not prevented by the Force Majeure event.

33. Change Orders and Contract Amendments

- 33.1 The Purchaser may at any time order the Supplier through notice in accordance GCC Clause 8, to make changes within the general scope of the Contract in any one or more of the following:
- (a) drawings, designs, or specifications, where Goods to be furnished under the Contract are to be specifically manufactured for the Purchaser:
- (b) the method of shipment or packing;
- (c) the place of delivery; and
- (d) the Related Services to be provided by the Supplier.
- 33.2 If any such change causes an increase or decrease in the cost of, or the time required for, the Supplier's performance of any provisions under the Contract, an equitable adjustment shall be made in the Contract Price or in the Delivery/Completion Schedule, or both, and the Contract shall accordingly be amended. Any claims by the Supplier for adjustment under this Clause must be asserted within twenty-eight (28) days from the date of the Supplier's receipt of the Purchaser's change order.
- 33.3 Prices to be charged by the Supplier for any Related Services that might be needed but which were not included in the Contract shall be agreed upon in advance by the parties and shall not exceed the prevailing rates charged to other parties by the Supplier for similar services.
- 33.4 Subject to the above, no variation in or modification of the terms of the Contract shall be made except by written amendment signed by the parties.

34. Extensions of Time

34.1 If at any time during performance of the Contract, the Supplier or its subcontractors should encounter conditions impeding timely delivery of the Goods or completion of Related Services pursuant to GCC Clause 13, the Supplier shall promptly notify

the Purchaser in writing of the delay, its likely duration, and its cause. As soon as practicable after receipt of the Supplier's notice, the Purchaser shall evaluate the situation and may at its discretion extend the Supplier's time for performance, in which case the extension shall be ratified by the parties by amendment of the Contract.

34.2 Except in case of Force Majeure, as provided under GCC Clause 32, a delay by the Supplier in the performance of its Delivery and Completion obligations shall render the Supplier liable to the imposition of liquidated damages pursuant to GCC Clause 26, unless an extension of time is agreed upon, pursuant to GCC Sub-Clause 34.1.

35. Termination 35.1 Termination for Default

- (a) The Purchaser, without prejudice to any other remedy for breach of Contract, by written notice of default sent to the Supplier, may terminate the Contract in whole or in part:
 - (i) if the Supplier fails to deliver any or all of the Goods within the period specified in the Contract, or within any extension thereof granted by the Purchaser pursuant to GCC Clause 34;
 - (ii) if the Supplier fails to perform any other obligation under the Contract; or
 - (iii) if the Supplier, in the judgment of the Purchaser has engaged in fraud and corruption, as defined in GCC Clause 3, in competing for or in executing the Contract.
- (b) In the event the Purchaser terminates the Contract in whole or in part, pursuant to GCC Clause 35.1(a), the Purchaser may procure, upon such terms and in such manner as it deems appropriate, Goods or Related Services similar to those undelivered or not performed, and the Supplier shall be liable to the Purchaser for any additional costs for such similar Goods or Related Services. However, the Supplier shall continue performance of the Contract to the extent not terminated.

35.2 Termination for Insolvency.

(a) The Purchaser may at any time terminate the Contract by giving notice to the Supplier if the Supplier becomes bankrupt or otherwise insolvent. In such event, termination will be without compensation to the Supplier, provided that such termination will not prejudice or affect any right of action or remedy that has accrued or will accrue thereafter to the purchase

- 35.3 Termination for Convenience.
- (a) The Purchaser, by notice sent to the Supplier, may terminate the Contract, in whole or in part, at any time for its convenience. The notice of termination shall specify that termination is for the Purchaser's convenience, the extent to which performance of the Supplier under the Contract is terminated, and the date upon which such termination becomes effective.
- (b) The Goods that are complete and ready for shipment within twenty-eight (28) days after the Supplier's receipt of notice of termination shall be accepted by the Purchaser at the Contract terms and prices. For the remaining Goods, the Purchaser may elect:
 - (i) to have any portion completed and delivered at the Contract terms and prices; and/or
 - (ii) to cancel the remainder and pay to the Supplier an agreed amount for partially completed Goods and Related Services and for materials and parts previously procured by the Supplier.

36. Assignment

36.1 Neither the Purchaser nor the Supplier shall assign, in whole or in part, their obligations under this Contract, except with prior written consent of the other party.

SECTION VIII. SPECIAL CONDITIONS OF CONTRACT

The following Special Conditions of Contract (SCC) shall supplement and / or amend the General Conditions of Contract (GCC). Whenever there is a conflict, the provisions herein shall prevail over those in the GCC.

GCC 1.1(j)	The Purchaser is: HASSAN DISTRICT COOPERATIVE MILK	
GCC 1.1(j)		
	PRODUCERS UNION LTD, HASSAN	
GCC 1.1 (o)	The Project Site(s)/Final Destination(s) is/are: AS PER ANNEXURE (A)	
	LIST OF DCS TO WHERE INSTALLATION TO BE DONE	
GCC 4.2 (a)	The meaning of the trade terms shall be as prescribed by Inco terms.	
GCC 4.2 (b)	The version edition of Inco terms shall be 2010	
GCC 8.1	For notices , the Purchaser's address shall be:	
	Attention: PURCHASE OFFICER	
	Address: PURCHASE DEPARTMENT,	
	HASSAN DIST. COOP.MILK PRODUCERS' UNION LTD, HASSAN	
	Floor/ Room number: CONFERENCE HALL -2	
	City: HASSAN	
	ZIP Code: 573201	
	Country: INDIA	
	Telephone: 08172-240628	
	Electronic mail address: <u>Hamul77@yahoo.com</u>	

GCC 10.2 Settlement of Disputes

The dispute settlement mechanism to be applied shall be as follows:

- (a) In case of Dispute or difference arising between the Purchaser and a domestic supplier relating to any matter arising out of or connected with this agreement, such disputes or difference shall be settled in accordance with the Arbitration and Conciliation Act, 1996. The arbitral tribunal shall consist of 3 arbitrators one each to be appointed by the Purchaser and the Supplier. The third Arbitrator shall be chosen by the two Arbitrators so appointed by the Parties and shall act as Presiding arbitrator. In case of failure of the two arbitrators appointed by the parties to reach upon a consensus within a period of 30 days from the appointment of the arbitrator appointed subsequently, the Presiding Arbitrator shall be appointed by the president of the institution of Engineers (India).
- (b) In the case of a dispute with a Foreign Supplier, the dispute shall be settled in accordance with provisions of UNCITRAL (United nations Commission on International Trade Law) Arbitration Rules. The Arbitral Tribunal shall consist of three Arbitrators one each to be appointed by the Purchaser and the Supplier. The third Arbitrator shall be chosen by the two Arbitrators so appointed by the parties, and shall act as presiding arbitrator. In case of failure of the two arbitrators appointed by the parties to reach upon a consensus within a period of 30 days from the appointment of the arbitrator appointed subsequently, the Presiding Arbitrator shall be appointed by the President of the Institution of Engineers (India).
- (c) If one of the parties fails to appoint its arbitrator in pursuance of subclause (a) and (b) above, within 30 days after receipt of the notice of the appointment of its arbitrator by the other party, then the president of the Institution of Engineers (India), both in cases of the Foreign supplier as well as Indian supplier, shall appoint the arbitrator. A certified copy of the order of the President of the Institution of Engineers (India), making such an appointment shall be furnished to each of the parties.

	(d) Arbitration proceedings shall be held at Hassan India, and the language of the arbitration proceedings and that of all documents and communications between the parties shall be English.
	(e) The decision of the majority of arbitrators shall be final and binding upon both parties. The cost and expenses of Arbitration proceedings will be paid as determined by the arbitral tribunal. However, the expenses incurred by each party in connection with the preparation, presentation etc. of its proceedings as also the fees and expenses paid to the arbitrator appointed by such party or on its behalf shall be borne by each party itself.
	(f) Where the value of the contract is Rs. 10 million and below, the disputes or differences arising shall be referred to the Sole Arbitrator. The Sole Arbitrator should be appointed by agreement between the parties; failing such agreement, by the appointing authority namely the President of the Institution of Engineers (India).
	(g) Except otherwise agreed to by the Parties, Arbitrators should give a decision in writing within 120 days of receipt of notification of dispute
GCC 12.1	The scope of supply for the Goods and Related Services to be supplied shall be as specified below: As per schedule of requirement and schedule of related services

GCC 13.1	Details of Shipping and other Documents to be furnished by the Supplier are given below: GCC 13.1 Upon delivery of the goods to the transporter/consignee,		
	the supplier shall notify the purchaser and mail the following documents to the Purchaser:		
	(i) 3 Copies of the Supplier invoice showing contract number, goods description, quantity, unit price, total amount;		
	(ii) Delivery note, Railway receipt, or Road consignment note or equivalent transport document or acknowledgement of receipt of goods from the Consignee;		
	(iii) 2 Copies of packing list identifying contents of each package; (iv) Insurance certificate;		
	(v) Manufacturer's/Supplier's warranty certificate;		
	(vi) Inspection certificate issued by the nominated inspection agency, and the Supplier's factory inspection report; as applicable		
	(vii) Certificate or origin.		
	(viii) Supplier should give the test certificate of S.S-304 And		
	Food grade quality hose pipe test certificate. (ix) supplier should also give the temperature indicator		
	certificate (calibration certificate) in every three months during warranty period		
	(x) Supplier also submits the BMC. lag-locking photos and		
	BMC tank gauge calibration certificate at the time of		
	commissioning by the authorize stamp & sign.		
	(xi) As per GPCB norms whole of the system of BMCU'S with all accessories must be qualified in GPCB terms &		
	conditions and supplier will also provides the GPCB		
	certificate of 37 quantities.		
	The above documents shall be received by the Purchaser before arrival of the Goods (except where it is handed over to		
	the Consignee with all documents) and if not received, the		
	supplier will be responsible for any consequent expenses.		
GCC 15.1	The prices charged for the Goods supplied and the related Services performed "shall not" be adjustable.		
GCC 16.1	GCC 16.1 Payment shall be made in Indian Rupees in the following manner:		

	(i) Eighty (80)% of the contract price shall be paid within 30days receipt of Goods and upon submission of the documents specified in Clause 13 of SCC; and		
	(ii) On Final Acceptance: the remaining twenty (20)% of the Contract Price shall be paid within thirty (30) days after the date of the Acceptance Certificate issued by the Purchaser's representative in the proforma given in Section VI - item 6.		
GCC 16.5	-DELETED-		
GCC 17	-DELETED-		
GCC 18.1	Performance Security to the Purchaser shall be for an amount of 10% of the contract value, valid up to 60 days after the date of completion of performance obligations including warranty obligations.		
	In the event of any correction of defects or replacement of defective material during the warranty period, the warranty for the corrected/replaced material shall be extended to a further period of 12 months and the Performance Bank guarantee for proportionate value shall be extended 60 days over and above the extended warranty period.		
GCC 18.3	The Performance Security shall be in the form of a "Bank Guarantee" drawn in favor of the Purchaser.		
GCC 18.4	Discharge of the performance Security shall take place not later than 60 days following the date of completion of the Supplier's performance obligations, including the warranty obligation, under the contract.		
GCC 18.5	Add as Clause 18.5 to the GCC the following: In the event of any contractual amendment, the Supplier shall, within 21 days of receipt of such amendment, furnish the amendment to the Performance Security, rendering the same valid for the duration of the Contract, as amended for 60 days after the completion of performance obligations including warranty obligations i.e. 5years.		
GCC 23.2	Packing Instructions: The Supplier will be required to make separate packages for each Consignee. Each package will be marked on three sides with proper paint/indelible ink with the following: (i) Project; (ii) Contract No.; (iii) Country of Origin of Goods; (iv) Supplier's Name; (v) Packing List Reference Number. Suppliers should use recycled materials as much as possible for packing		
GCC 24.1	The insurance shall be paid in an amount equal to 110 percent of the EXW value of the Goods from "Warehouse to warehouse (final destination)" on "All Risks" basis including War Risks and Strikes.		
GCC 25.1	The Supplier is required under the Contract to transport the Goods duly insured to the specified final destination, and all related costs shall be included in the Contract Price.		

	The inspections and tests shall be:			
GCC 26.1				
	Nature- inspection of Goods of BMC			
	Frequency- At the time of installation & commissioning of BMC.			
	Procedures- Hassan dairy officer's and Company technician both			
	together inspect the Goods of BMC.			
	Nature- Test- Performance test of BMC			
	Frequency- Six months after the installation & commissioning of			
	BMC			
	Procedure: Hassan dairy officer's and Company technician both			
	together will take the performance test of BMC. In performance test,			
	time of cooling & unit consumed by BMC will be taken in calculation.			
	After this test, conclusion showing the result of BMC			
GCC 26.2	The Inspections and tests shall be conducted at: As per Annexure A			
GCC 27.1 The liquidated damage shall be: 0.5% of the value of the delay				
	only for each completed week of delay.			
GCC 27.2	The maximum amount of liquidated damages shall be: 10% of the			
	Contract price.			
GCC 28.3	The warranty should be 24 months from the date of supply &			
	18 months from the date of commissioning whichever is earlier.			
	The period for repair or replacement shall be within 24 hours. If complaint			
GCC 28.5	will not resolve within 24 hours, supplier must pay the Amount in form of			
	penalty of Deteriorated milk quantity & also pay the transportation cost			
	of milk send by cans.			
GCC 31.1	This clause will apply only to variations in GST payable in India on			
	the final product which is being supplied and not for the individual			
	components / raw materials which go into the product.			

SECTION IX – CONTRACT FORMS

Table of Forms

1.	CONTRACT AGREEMENT	.104
2.	PERFORMANCE SECURITY	.106
3.	BANK GUARANTEE FOR ADVANCE PAYMENT	.106

1. CONTRACT AGREEMENT

[The successful Bidder shall fill in this form in accordance with the instructions indicated]

THIS CONTRACT AGREEMENT is made

the [insert: number] day of [insert: month], [insert: year].

BETWEEN

- [insert complete name of Purchaser], a [insert description of type of legal entity, for example, an agency of the Ministry of of the Government of {insert name of Country of Purchaser}, or corporation incorporated under the laws of {insert name of Country of Purchaser}] and having its principal place of business at [insert address of Purchaser] (hereinafter called "the Purchaser"), and
- (2) [insert name of Supplier], a corporation incorporated under the laws of [insert: country of Supplier] and having its principal place of business at [insert: address of Supplier] (hereinafter called "the Supplier").

WHEREAS the Purchaser invited bids for certain Goods and ancillary services, viz., [insert brief description of Goods and Services] and has accepted a Bid by the Supplier for the supply of those Goods and Services in the sum of [insert Contract Price in words and figures, expressed in the Contract currency(ies)] (hereinafter called "the Contract Price").

NOW THIS AGREEMENT WITNESSETH AS FOLLOWS:

- 1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract referred to.
- 2. The following documents shall constitute the Contract between the Purchaser and the Supplier, and each shall be read and construed as an integral part of the Contract:
- (a) This Contract Agreement
- (b) Special Conditions of Contract
- (c) General Conditions of Contract
- (d) Technical Requirements (including Schedule of Requirements and Technical Specifications)
- (e) The Supplier's Bid and original Price Schedules
- (f) The Purchaser's Notification of Award
- (g) [Add here any other document(s)]
- 3. This Contract shall prevail over all other Contract documents. In the event of any discrepancy or inconsistency within the Contract documents, then the documents shall prevail in the order listed above.

- 4. In consideration of the payments to be made by the Purchaser to the Supplier as hereinafter mentioned, the Supplier hereby covenants with the Purchaser to provide the Goods and Services and to remedy defects therein in conformity in all respects with the provisions of the Contract.
- 5. The Purchaser hereby covenants to pay the Supplier in consideration of the provision of the Goods and Services and the remedying of defects therein, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

IN WITNESS whereof the parties hereto have caused this Agreement to be executed in accordance with the laws of [insert the name of the Contract governing law country] on the day, month and year indicated above.

For and on behalf of the Purchaser

Signed: [insert signature] in the capacity of [insert title or other appropriate designation] in the presence of [insert identification of official witness]

For and on behalf of the Supplier

Signed: [insert signature of authorized representative(s) of the Supplier] in the capacity of [insert title or other appropriate designation] in the presence of [insert identification of official witness]

2. PERFORMANCE SECURITY

[The bank, as requested by the successful Bidder, shall fill in this form in accordance with the instructions indicated]

Date: [insert date (as day, month, and year) of Bid Submission] ICB No. and title: [insert no. and title of bidding process]

Bank's Branch or Office: [insert complete name of Guarantor]

Beneficiary: [insert complete name of Purchaser]

PERFORMANCE GUARANTEE No.: [insert Performance Guarantee number]

We have been informed that [insert complete name of Supplier] (hereinafter called "the Supplier") has entered into Contract No. [insert number] dated [insert day and month], [insert year] with you, for the supply of [description of Goods and related Services] (hereinafter called "the Contract").

Furthermore, we understand that, according to the conditions of the Contract, a Performance Guarantee is required.

At the request of the Supplier, we hereby irrevocably undertake to pay you any sum(s) not exceeding [insert amount(s^2) in figures and words] upon receipt by us of your first demand in writing declaring the Supplier to be in default under the Contract, without cavil or argument, or your needing to prove or to show grounds or reasons for your demand or the sum specified therein.

This Guarantee shall expire no later than the [insert number] day of [insert month] [insert year],³ and any demand for payment under it must be received by us at this office on or before that date.

This guarantee is subject to the Uniform Rules for Demand Guarantees, ICC Publication No. 458, except that subparagraph (ii) of Sub-article 20(a) is hereby excluded.

[signatures of authorized representatives of the bank and the Supplier]

1. The most current listing of eligible countries can be viewed on the Public Information Center's Web page at: http://www.worldbank.org/html/pic/PROCURE.html. A list of firms debarred from participating in World Bank projects is available at: http://www.worldbank.org/html/opr/procure/debarr.html.

 Any questions regarding this list should be addressed to the Senior Manager, Procurement Policy and Services Group, Operational Core Services Network, The World Bank

The Bank shall insert the amount(s) specified in the SCC and denominated, as specified in the SCC, either in the currency(ies) of the Contract or a freely convertible currency acceptable to the Purchaser.

Dates established in accordance with Clause 17.4 of the General Conditions of Contract ("GCC"), taking into account any warranty obligations of the Supplier under Clause 15.2 of the GCC intended to be secured by a partial Performance Guarantee. The Purchaser should note that in the event of an extension of the time to perform the Contract, the Purchaser would need to request an extension of this Guarantee from the Bank. Such request must be in writing and must be made prior to the expiration date established in the Guarantee. In preparing this Guarantee, the Purchaser might consider adding the following text to the Form, at the end of the penultimate paragraph: "We agree to a one-time extension of this Guarantee for a period not to exceed [six months] [one year], in response to the Purchaser's written request for such extension, such request to be presented before theexpiry oftheGuarantee." tous

Annexure-A"Final destination (Project Site)":LIST OF VILLAGE LEVEL DAIRY COOPERATIVE SOCIETIES(WDCS) TO WHERE BMCU's TO BE INSTALLED

	ERATIVE SOCIETIES (VDCS) TO VIIIE			
Sr.	Name of DCS proposed for BMC installation	Tahsil	Dist	Capacity
No	(Mention the DCS name corresponding	Name	Name	(KL)
	to the Village name in Coloumn D, rows may be added in case there are more			
	than one DCS in one village)			
1	Paduvalahippe	H N Pura	Hassan	5 KL
2	Mavanuru	H N Pura	Hassan	3 KL
3	Banukuppe	H N Pura	Hassan	3 KL
4	Malali	H N Pura	Hassan	3 KL
5	Parasanahalli	H N Pura	Hassan	3 KL
6	Chakenahalli	H N Pura	Hassan	3 KL
7	Doddakunchevu	H N Pura	Hassan	3 KL
8	Kodihalli	H N Pura	Hassan	3 KL
9	Kallahalli	H N Pura	Hassan	3 KL
10	H Hindalahalli	H N Pura	Hassan	3 KL
11	Badkyatanahalli	H N Pura	Hassan	3 KL
12	Bandiganahalli	H N Pura	Hassan	3 KL
13	Baragur	Arakalgud	Hassan	5 KL
14	Nilakunda	Arakalgud	Hassan	3 KL
15	Thejuru	Arakalgud	Hassan	3 KL
16	Mallinathapura	Arakalgud	Hassan	3 KL
17	Maduranahalli	Arakalgud	Hassan	3 KL
18	Bislehalli	Arakalgud	Hassan	3 KL
19	Honnavalli	Arakalgud	Hassan	3 KL
20	Nygere	Arakalgud	Hassan	3 KL
21	Kalenahalli	Arakalgud	Hassan	3 KL
22	Nilavagilu	Arakalgud	Hassan	3 KL
23	Doddabyadigere	Belur	Hassan	3 KL
24	Gonisomanahalli	Belur	Hassan	3 KL
25	Virupayyanakoppalu	Belur	Hassan	5 KL
26	Kalyanpura	Belur	Hassan	3 KL
27	Ibbeedu	Belur	Hassan	3 KL
28	Sankenahalli	Belur	Hassan	3 KL
29	Ganjigere	Alur	Hassan	5 KL
30	Dharmapuri	Alur	Hassan	3 KL
31	Kanathuru	Alur	Hassan	3 KL
32	Kamathikudige	Alur	Hassan	3 KL
33	Hullahalli	Alur	Hassan	3 KL
34	Hunasavalli	Alur	Hassan	3 KL
35	Karehalli	C R Patna	Hassan	3 KL
36	Santheshivara	C R Patna	Hassan	5 KL
37	Yachanagatta	C R Patna	Hassan	3 KL

Sr.	Name of DCS proposed for BMC installation	Tahsil	Dist	Capacity
No	(Mention the DCS name corresponding	Name	Name	(KL)
	to the Village name in Coloumn D, rows			
	may be added in case there are more than one DCS in one village)			
20	0 /	G D D	**	2 777
38	M Dasapura	C R Patna	Hassan	3 KL
39	D.Tumakuru	C R Patna	Hassan	3 KL
40	H G Koppalu	Hassan	Hassan	3 KL
41	Siddapura	Hassan	Hassan	3 KL
42	Bandihalli	Hassan	Hassan	3 KL
43	Doddabeekanahalli	Hassan	Hassan	5 KL
44	Nayakarahalli	Hassan	Hassan	3 KL
45	Karle	Hassan	Hassan	3 KL
46	Kadalamagge	Arasikere	Hassan	3 KL
47	Handralu	Arasikere	Hassan	3 KL
48	M C Halli	Tarikere	Chikmagalur	3 KL
49	Rangenahalli	Tarikere	Chikmagalur	3 KL
50	Arasikere Colony	Tarikere	Chikmagalur	3 KL

Annexure B- Deviation/Non-Compliance Statement

(Please give all deviations and/or non-compliance clause wise statement against the said Tender document in the format given below)

Tender No:

Sr. No.	Section/Article/ Clause	Statement of Deviation

Note:

- In case of any other deviation not mentioned on this page may lead to disqualifying of Bid
- Mentioning Deviation in above mentioned format does not ensure its acceptance by Hassan Dairy
- · Above mentioned format is indicative and supplier can furnish above required information in their own form